



1 **TERMINAL AIR BOX - SINGLE DUCT**
NO SCALE

- NOTES:
1. THIS DETAIL APPLIES ONLY TO TAPS OFF WRAPPED DUCTS.
 2. THIS DETAIL APPLIES TO TERMINAL AIR BOXES WITH ROUND INLETS AND RECTANGULAR OUTLETS.
 3. DUCT LEADING TO TAB INLET MUST BE STRAIGHT FOR 1.5 DIAMETER UPSTREAM.
 4. MAINTAIN VAPOR BARRIER FROM MAIN TO BRANCH DUCT.




2 **COIL - IN DUCT HEATING - WRAPPED**
NO SCALE

- NOTES:
1. THIS DETAIL APPLIES TO ALL HEATING COILS INSTALLED IN DUCTS. ACCESS DOORS AND FLANGED CONNECTIONS MUST BE PROVIDED AT ALL COILS UNLESS SPECIFICALLY NOTED OTHERWISE.
 2. PROVIDE FLANGED CONNECTION ON BOTH SIDES OF COILS. ACCESS DOORS ARE ONLY REQUIRED UPSTREAM OF COILS.
 3. PROVIDE 48\"/>




3 **FAN/HOOD CURB ROOF SUPPORT DETAIL**
NO SCALE

- NOTES:
1. ALL ROOF FLASHING SHALL BE PER ROOF MANUFACTURER'S RECOMMENDATIONS.




4 **EXHAUST STACK THROUGH ROOF**
NO SCALE

- NOTES:
1. MAINTAIN A MINIMUM 1\"/>



5 **DUCT ROOF PENETRATION**
NO SCALE

- NOTES:
1. ALL ROOF FLASHING SHALL BE PER ROOF MANUFACTURER'S RECOMMENDATIONS.



6 **HIGH PLUME EXHAUST FAN ROOF SUPPORT DETAIL**
NO SCALE

Revisions:	Date:

CONSULTANT

IMEG

1000 SOUTH STREET
DIX HOLLOW PLAZA
MILWAUKEE, WI 53214
www.imeg.com
PROJECT # 18060404


WE COPY DESIGN OR INVENTION RIGHTS, INCLUDING COMPROMISE TO THIS CONTRACT AND THE DESIGN TO PERSONS AND COMPANIES WHO ARE NOT EMPLOYEES OF IMEG OR OUR AFFILIATES. WE WILL NOT BE RESPONSIBLE FOR ANY LOSS OR DAMAGE TO ANY PROPERTY OR PERSONS THAT MAY BE CAUSED BY THE USE OF THIS DESIGN OR INVENTION. THIS CONTRACT IS VOID IF ANY OTHER CONTRACT IS USED WITHOUT THE EXPRESS WRITTEN PERMISSION OF IMEG OR OUR AFFILIATES.

PROFESSIONAL SCALE BY IMEG

ARCHITECT/ENGINEER OF RECORD

ANDERSON

18605 3rd Ave. N. #100 Plymouth, MN 55441
P 788.432.4080 | F 788.432.4500 | anderson.com
Anderson Engineering & Architecture, LLC | P&E # 16064



Office of Construction and Facilities Management

VA U.S. Department of Veterans Affairs

Drawing Title	VENTILATION DETAILS
Approved:	


Phase	BID DOCUMENTS
FULLY SPRINKLERED	

Project Title	CONSTRUCT NEW SPS	Project Number	438-460
		Building Number	5
		Drawing Number	MV401
Location	Sioux Falls, SD	Issue Date	02/14/2025
		Checked	DAVING
		Drawn	DELLE

24-10000-10/2025 (Rev. 08-2021) VA FORM 08-6221


1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10

A




PLAN VIEW

B



PLAN VIEW

C




ELEVATION VIEW

D


1 AHU-1 COMPONENT DETAIL

E




3 AHU-1 ISOMETRIC LOOKING NORTHWEST

F



ELEVATION VIEW

2 AHU-2 COMPONENT DETAIL



4 AHU-2 ISOMETRIC LOOKING SOUTHEAST

Revisions:	Date:

CONSULTANT

IMEG

1805 SOUTH STREET
 SUITE 2000 - 2ND FLOOR
 414 BROADWAY, SUITE 2000
 MINNEAPOLIS, MN 55402
 WWW.IMEG.COM
 PROJECT # 180502000


WE COPY DESIGN OR INVENTION RIGHTS, INCLUDING COMPANIES, TO THIS CONTRACT AND THE DESIGN PROFESSIONAL. ANY DESIGN OR INVENTION OR INTELLECTUAL PROPERTY RIGHTS ARE RESERVED BY THE DESIGN PROFESSIONAL. ANY DESIGN OR INVENTION OR INTELLECTUAL PROPERTY RIGHTS ARE RESERVED BY THE DESIGN PROFESSIONAL.

PROPOSED SCALE: AS SHOWN

ARCHITECT/ENGINEER OF RECORD

ANDERSON

1805 3rd Ave. N., 2120 Plymouth, MN 55441
 P 783.432.4000 | F 788.432.4000 | anderson.com
 Anderson Engineering Co. Minneapolis, MN | PEO # 16064



Office of Construction and Facilities Management


VA U.S. Department of Veterans Affairs

Drawing Title	VENTILATION DETAILS
Approved:	

Phase	BID DOCUMENTS
Project Title	CONSTRUCT NEW SPS
Location	Sioux Falls, SD
Issue Date	02/14/2025
Checked	DAVING
Drawn	DELLE

Project Number	438-460
Building Number	5
Drawing Number	MV402

- GENERAL PIPING DEMOLITION NOTES:**
1. REFERENCE MP00 - PIPING COVER SHEET FOR PIPING SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
 2. EXISTING CONDITIONS ARE SHOWN BASED ON INFORMATION OBTAINED FROM FIELD SURVEYS, EXISTING BUILDING DOCUMENTS, AND STAFF. VERIFY EXISTING CONDITIONS AND REPORT ANY CONFLICTS BEFORE PROCEEDING.
 3. COMPLETE LAYOUT DRAWINGS SHALL BE REQUIRED BY SPECIFICATION SECTION 05100 UNTIL SYSTEM LAYOUT DRAWINGS HAVE BEEN APPROVED BY THE U.S.A.
 4. CONTRACTOR SHALL MINIMIZE DOWNTIME OF EXISTING SYSTEMS BY INSTALLING NEW SYSTEMS PRIOR TO TYING INTO EXISTING. NOTIFY C.O.A. A MINIMUM OF 24 HOURS PRIOR TO SYSTEM SHUTDOWN.
 5. DEMOLISH ALL EXISTING HANGERS, RADIATION, DAMPERS, AND ACCESSORIES ASSOCIATED WITH MECHANICAL EQUIPMENT, DUCTWORK, AND PIPING SHOWN TO BE REMOVED ON THESE PLANS UNLESS OTHERWISE NOTED.
 6. DEMOLISH ALL EXISTING CONTROL DEVICES, WIRING, AND CONDUIT ASSOCIATED WITH MECHANICAL EQUIPMENT SHOWN TO BE REMOVED ON THESE PLANS UNLESS OTHERWISE NOTED.
 7. NOT ALL MECHANICAL DEMOLITION IS EXPLICITLY SHOWN ON THE DRAWING. CONTRACTOR SHALL CONFIRM EXTENT OF DEMOLITION AT THE SITE.
- KEYNOTES: (1)**
1. EXISTING HEATING WATER PIPING IS ROUTED ON FLOOR IN STAIRWELL PRIOR TO RISING UP STAIR TOWER. REMOVE PIPING ROUTED ON FLOOR AND REPAIR RISERS ABOVE GROUND FLOOR FOR RE-CONNECTION.
 2. EXISTING AIR-COOLED CONDENSING UNITS PERFORMING SERVICE AS A MODULAR CHILLER LOCATED IN THE 8TH LEVEL ATTIC SPACE WHICH HAS BEEN TRANSFERRED TO A NEW COOLING TOWER. CHILLERS SHALL BE REMOVED FROM EXISTING LOCATION. COORDINATE REMOVAL OF CHILLERS WITH CONTRACTING OFFICERS REPRESENTATIVE. PROPERLY RECLAIM AND DISPOSE OF ALL REFRIGERANT.



1 GROUND LEVEL FLOOR DEMOLITION PLAN - PIPING



PIPEING FOR FOUR REFRIGERANT CIRCUITS UP EXTERIOR WALL TO ATTIC



REMOVE POWER AND CONTROL CONDUITS COORDINATE WITH ELECTRICAL CONTRACTOR
REMOVE REFRIGERANT PIPING
REMOVE PIPE SUPPORT BRACKETS. COORDINATE WALL PATCHING WITH ARCHITECT

2 EXISTING REFRIGERANT PIPING DEMOLITION DETAIL

2/14/2025 10:57:45 AM
 2/14/2025 10:57:45 AM
 2/14/2025 10:57:45 AM

Revisions:	Date:

CONSULTANT

IMEG


1800 SOUTH STREET
 SUITE 1000
 11425 W. 114TH AVE. SUITE 1000
 PROJECT # 1800000000

MEG COMPANY DESIGNATED PROJECTS: MECHANICAL, ELECTRICAL, PLUMBING, AND PIPING. ALL OTHERS ARE THE RESPONSIBILITY OF THE CLIENT. MECHANICAL, ELECTRICAL, PLUMBING, AND PIPING. ALL OTHERS ARE THE RESPONSIBILITY OF THE CLIENT.

ARCHITECT/ENGINEER OF RECORD

ANDERSON

18605 3rd Ave. W., 8100 Plymouth, MN 55441
 P 788.432.4000 | F 788.432.4000 | anderson.com
 Anderson Engineering of Minnesota, LLC | PWS # 16004



Office of Construction and Facilities Management


VA U.S. Department of Veterans Affairs

Drawing Title	GROUND LEVEL FLOOR DEMOLITION PLAN - PIPING
Approved:	

Phase	BID DOCUMENTS
Project Title	CONSTRUCT NEW SPS
Location	Sioux Falls, SD
Issue Date	02/14/2025
Checked	DAVING
Drawn	DELLE

Project Number	438-460
Drawing Number	5
Drawing Number	MPD101

- GENERAL PIPING DEMOLITION NOTES**
1. REFERENCE MP100 - PIPING COVER SHEET FOR PIPING SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
 2. EXISTING CONDITIONS ARE SHOWN BASED ON INFORMATION OBTAINED FROM FIELD SURVEYS, EXISTING BUILDING DOCUMENTS, AND STAFF. VERIFY EXISTING CONDITIONS AND REPORT ANY CONFLICTS BEFORE PROCEEDING.
 3. COMPLETE LAYOUT DRAWINGS SHALL BE REQUIRED BY SPECIFICATION SECTION 05.05 UNTIL SYSTEM LAYOUT DRAWINGS HAVE BEEN APPROVED BY THE S.C.D.R.
 4. CONTRACTOR SHALL MINIMIZE DOWNTIME OF EXISTING SYSTEMS BY INSTALLING NEW SYSTEMS PRIOR TO TYING INTO EXISTING. NOTIFY C.O.R. A MINIMUM OF 24 HOURS PRIOR TO SYSTEM SHUTDOWN.
 5. DEMOLISH ALL EXISTING HANGERS, REGULATION, DAMPERS, AND ACCESSORIES ASSOCIATED WITH MECHANICAL EQUIPMENT, DUCTWORK, AND PIPING SHOWN TO BE REMOVED ON THESE PLANS UNLESS OTHERWISE NOTED.
 6. DEMOLISH ALL EXISTING CONTROL DEVICES, WIRING, AND CONDUIT ASSOCIATED WITH MECHANICAL EQUIPMENT SHOWN TO BE REMOVED ON THESE PLANS UNLESS OTHERWISE NOTED.
 7. NOT ALL MECHANICAL DEMOLITION IS EXPLICITLY SHOWN ON THE DRAWING. CONTRACTOR SHALL CONFIRM EXTENT OF DEMOLITION AT THE SITE.



1 FIRST LEVEL DEMOLITION PLAN - PIPING
1/8" = 1'-0"

2/16/2025 10:27:41 AM
 2/16/2025 10:27:41 AM
 2/16/2025 10:27:41 AM

Revisions:	Date:

CONSULTANT

IMEG

1800 SOUTH STREET
 SUITE 1000
 SIOUX FALLS, SD 57105
 P 605.336.1111
 WWW.IMEGSD.COM

DATE: 02/14/2025
 PROJECT: CONSTRUCT NEW SPS

SCALE: AS SHOWN

ARCHITECT/ENGINEER OF RECORD

ANDERSON

1860 S 3rd Ave. W. 57105
 P 605.332.4000 | F 605.332.4000 | www.a-e.com
 Anderson Engineering & Architecture, LLC | PWS # 16004

STAMP

PROFESSIONAL ENGINEER
 STATE OF SOUTH DAKOTA
 LEWELLEN
 2175
 SIOUX FALLS, SD 57104

Office of Construction and Facilities Management

VA U.S. Department of Veterans Affairs

Drawing Title
 FIRST LEVEL DEMOLITION PLAN - PIPING

Approved:

Phase
 BID DOCUMENTS

FULLY SPRINKLERED

Project Title
 CONSTRUCT NEW SPS

Location
 Sioux Falls, SD

Issue Date
 02/14/2025


Checked
 DAVING

Drawn
 DELLE

Project Number
 438-460

Building Number
 5

Drawing Number
 MPD111



- GENERAL MECHANICAL NOTES:**
1. REFERENCE MP000 - PIPING COVERSHEET FOR VENTILATION SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
 2. COORDINATE AND CONFIRM ALL ARCHITECTURALLY EXPOSED DEVICE LOCATIONS WITH ARCHITECT PRIOR TO ROUGH-IN OR INSTALLATION. REFERENCE MP500 FOR STEAM FLOW DIAGRAM.
 3. REFERENCE MP501 FOR HEATED WATER FLOW DIAGRAM.
 4. REFERENCE MP502 FOR CHILLED WATER FLOW DIAGRAM.
 5. REFERENCE MP503 FOR PIPING SCHEDULES. COMPLETE LAYOUT DRAWINGS SHALL BE REQUIRED BY SPECIFICATION SECTION 25.05. UNLESS OTHERWISE NOTED, ALL PIPING SHALL BE INSTALLED IN ACCORDANCE WITH THE C.O.R.
 6. ALL PIPING OF ANY KIND ABOVE SOLIDID CEILING SHALL BE CONSTRUCTED OF AS FEW PIECES AS POSSIBLE AND SHALL ONLY UTILIZE WELDED OR BREADED JOINTS AND CONNECTIONS.
 7. REFERENCE TMR400 FOR PIPE HANGERS AND SUPPORTS DETAIL.
 8. REFERENCE TMR400 FOR FIRE RATED FLOOR/WALL PENETRATION DETAIL.
 9. REFERENCE TMR400 FOR NON-FIRE RATED WALL PENETRATION DETAIL.
- KEYNOTE (K):**
1. REFERENCE TMR401 FOR HEATING WATER COIL PIPING DIAGRAM WITH SHAW VALVE.
 2. REFERENCE TMR401 FOR HEATING WATER COIL PIPING DIAGRAM WITH SHAW VALVE.
 3. MECHANICAL CONTRACTOR SHALL PROVIDE SNOW MELT TUBING BEDDING IN CONCRETE WALKWAY REFERENCE RADIATION ZONE SCHEDULE ON PIPING FOR PERFORMANCE CRITERIA. REFERENCE TMR401 FOR SNOW MELT TUBING DETAIL.
 4. SNOW MELT MANUFACTURER SHALL PROVIDE SNOW AND ICE SENSOR FOR INSTALLATION BY MECHANICAL CONTRACTOR. REFERENCE TMR401 FOR RADIANT SLAB SENSOR DETAIL.
 5. CONCRETE SNOWMELT TUBING IN CHASE SHALL BE SHIELD WITH SHEET METAL PLATING FROM FLOOR TO CEILING TO PREVENT FUTURE INCIDENTAL PUNCTURES.
 6. PROVIDE MEDIAN PRESSURE STEAM HOSE HOSE STATION PIPED WITH SOFT COLD WATER. COORDINATE EXACT LOCATION WITH ARCHITECT AND PLUMBING CONTRACTOR. PIPING CONTRACTOR TO PROVIDE MOVING VALVE AND SHELLED HOSE.
 7. STERILIZER WILL BE RELOCATED BY THE EQUIPMENT VENDOR FROM AN EXISTING LOCATION IN THE FACILITY TOWARDS THE END OF THE PROJECT. ALL PIPING SHALL BE RELOCATED IN PRIOR TO RELOCATION TO MINIMIZE DOWN TIME OF THE EQUIPMENT. COORDINATE WITH C.O.R. FOR RELOCATION EFFORT.

1 GROUND LEVEL FLOOR PLAN - PIPING

2/14/2025 10:27:03 AM
 2/14/2025 10:27:03 AM
 2/14/2025 10:27:03 AM

Revisions:	Date:

CONSULTANT

IMEG

1800 SOUTH STREET
 SUITE 2000
 HOUSTON, TEXAS 77058
 PHONE: 713.261.1111
 WWW.IMEG.COM

ALL COPY RIGHTS ARE RESERVED BY IMEG. ANY REPRODUCTION OR TRANSMISSION OF THIS DOCUMENT OR THE DATA HEREIN WITHOUT THE WRITTEN PERMISSION OF IMEG IS STRICTLY PROHIBITED. FOR ANY OTHER PROJECTS, CONTACT THE PROJECT MANAGER.

PROJECT # 180441


DATE: 02/14/2025

SCALE: AS SHOWN

ARCHITECT/ENGINEER OF RECORD

ANDERSON

1805 3rd Ave. N. #1500
 FARGO, ND 58103
 P: 701.785.4324
 F: 701.785.4324
 WWW.ANDERSON-ND.COM



Office of Construction and Facilities Management

VA U.S. Department of Veterans Affairs

Drawing Title	GROUND LEVEL FLOOR PLAN - PIPING
Approved:	


Phase	BID DOCUMENTS
	FULLY SPRINKLERED

Project Title	CONSTRUCT NEW SPS	Project Number	438-460
		Drawing Number	5
Location	Sioux Falls, SD	Drawing Number	MP101
Issue Date	02/14/2025	Checked	DAVING
		Drawn	DELLE


- GENERAL MECHANICAL NOTES:**
1. REFERENCE MP000 - PIPING COVERSHEET FOR VENTILATION SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
 2. COORDINATE AND CONFIRM ALL ARCHITECTURALLY EXPOSED DEVICE LOCATIONS WITH ARCHITECT PRIOR TO ROUGH-IN OR INSTALLATION. REFERENCE MP500 FOR STEAM FLOW DIAGRAM.
 3. REFERENCE MP501 FOR HEATING WATER FLOW DIAGRAM.
 4. REFERENCE MP502 FOR CHILLED WATER FLOW DIAGRAM.
 5. REFERENCE MP503 FOR PIPING SCHEDULES.
 6. COMPLETE LAYOUT DRAWINGS SHALL BE REQUIRED BY SPECIFICATION SECTION 05 11. CONSTRUCTION WORK SHALL NOT BEGIN UNTIL SYSTEM LAYOUT DRAWINGS HAVE BEEN APPROVED BY THE C.O.R.
 7. ALL PIPING OF ANY KIND ABOVE SOLID LID CEILING SHALL BE CONSTRUCTED OF AS FEW PIECES AS POSSIBLE AND SHALL ONLY UTILIZE WELDED OR BREADED JOINTS AND CONNECTIONS.
 8. REFERENCE TAMP400 FOR PIPE HANGERS AND SUPPORTS DETAIL.
 9. REFERENCE TAMP400 FOR FIRE RATED FLOORWALL PENETRATION DETAIL.
 10. REFERENCE TAMP400 FOR NON-FIRE RATED WALL PENETRATION DETAIL.
 11. REFERENCE TAMP400 FOR SHELL & TUBE HEAT EXCHANGER PIPING DETAIL.
 12. REFERENCE TAMP400 FOR PLATE & FRAME HEAT EXCHANGER PIPING DETAIL.
 13. REFERENCE TAMP400 FOR INSULATED PIPE HOUSING ROOF PENETRATION DETAIL.
 14. REFERENCE TAMP400 FOR HEAT EXCHANGER SUPPORT DETAIL.
 15. REFERENCE TAMP400 FOR 4-PPE FAN COIL UNIT PIPING DIAGRAM.
 16. REFERENCE TAMP400 FOR SNOW MELT MANIFOLD PIPING DETAIL.
 17. REFERENCE TAMP400 FOR HEATING WATER COIL PIPING DIAGRAM WITH 3-WAY VALVE.
 18. REFERENCE TAMP400 FOR HEATING WATER COIL PIPING DIAGRAM WITH 3-WAY VALVE PROVIDE PLUT SYSTEM OUTDOOR UNIT WITH WALL HANGING MOUNTING BRACKET MOUNT APPROXIMATELY 2" ABOVE TOP OF ROOF INSULATION.

KEYNOTE:

1. REFERENCE TAMP400 FOR SHELL & TUBE HEAT EXCHANGER PIPING DETAIL.
2. REFERENCE TAMP400 FOR PLATE & FRAME HEAT EXCHANGER PIPING DETAIL.
3. REFERENCE TAMP400 FOR INSULATED PIPE HOUSING ROOF PENETRATION DETAIL.
4. REFERENCE TAMP400 FOR HEAT EXCHANGER SUPPORT DETAIL.
5. REFERENCE TAMP400 FOR 4-PPE FAN COIL UNIT PIPING DIAGRAM.
6. REFERENCE TAMP400 FOR SNOW MELT MANIFOLD PIPING DETAIL.
7. REFERENCE TAMP400 FOR HEATING WATER COIL PIPING DIAGRAM WITH 3-WAY VALVE.
8. REFERENCE TAMP400 FOR HEATING WATER COIL PIPING DIAGRAM WITH 3-WAY VALVE PROVIDE PLUT SYSTEM OUTDOOR UNIT WITH WALL HANGING MOUNTING BRACKET MOUNT APPROXIMATELY 2" ABOVE TOP OF ROOF INSULATION.




1 INTERSTITIAL/FIRST LEVEL FLOOR PLAN - PIPING
1/8" = 1'-0"



2 ENLARGED INTERSTITIAL/FIRST LEVEL FLOOR PLAN - PIPING
1/4" = 1'-0"

Revisions: _____ Date: _____	CONSULTANT <small> IMEG Mechanical Engineering 1000 S. GARDNER STREET SIOUX FALLS, SD 57105 P 605.336.1234 F 605.336.1235 WWW.IMEG-SD.COM </small>	ARCHITECT/ENGINEER OF RECORD <small> 1860S 3rd Ave. W., 8120 Plymouth, MN 55441 P 763.432.4080 F 763.432.4090 www.a-e.com Anderson Engineering Co. Minneapolis, LLC PE# 0116064 </small>	STAMP 	Office of Construction and Facilities Management U.S. Department of Veterans Affairs	Drawing Title INTERSTITIAL/FIRST LEVEL FLOOR PLAN - PIPING Approved: _____	Phase BID DOCUMENTS FULLY SPRINKLERED	Project Title CONSTRUCT NEW SPS Location Sioux Falls, SD Issue Date 02/14/2025 Checked DAVING Drawn DELLE	Project Number 438-460 Drawing Number 5 Drawing Number MP111
------------------------------	---	--	------------------	--	--	---	---	--

- GENERAL MECHANICAL NOTES:**
- REFERENCE MP000 - PIPING COVERSHEET FOR VENTILATION SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
 - COORDINATE AND CONFIRM ALL ARCHITECTURALLY EXPRESSED DEVICE LOCATIONS WITH ARCHITECT PRIOR TO ROUGH-IN OR INSTALLATION. REFERENCE MP000 FOR STEAM FLOW DIAGRAM.
 - REFERENCE MP001 FOR HEATING WATER FLOW DIAGRAM.
 - REFERENCE MP002 FOR CHILLED WATER FLOW DIAGRAM.
 - REFERENCE MP003 FOR PIPING SCHEDULES. COMPLETE LAYOUT DRAWINGS SHALL BE REQUIRED BY SPECIFICATION SECTION 05 11. CONSTRUCTION WORK SHALL NOT BEGIN UNTIL SYSTEM LAYOUT DRAWINGS HAVE BEEN APPROVED BY THE C.O.R.
 - ALL PIPING OF ANY KIND ABOVE SOLID LID CEILING SHALL BE CONSTRUCTED OF AS FEW PIECES AS POSSIBLE AND SHALL ONLY UTILIZE WELDED OR BREADED JOINTS AND CONNECTIONS.
 - REFERENCE TMR400 FOR PIPE HANGERS AND SUPPORTS DETAIL.
 - REFERENCE TMR400 FOR FIRE RATED FLOORWALL PENETRATION DETAIL.
 - REFERENCE TMR400 FOR NON-FIRE RATED WALL PENETRATION DETAIL.
- KEYNOTE: (K)**
- ROUTE REFRIGERANT PIPING ACROSS ROOF. FOLLOW CHILLER MANUFACTURER'S REQUIREMENTS FOR REFRIGERANT PIPE ROUTING AND SIZING. EXTERIOR REFRIGERANT PIPING SHALL BE INSULATED AND WRAPPED WITH ALUMINUM JACKETING. REFERENCE TMR400 FOR EXTERIOR PIPING ROOF SUPPORT DETAIL. REFERENCE TMR400 FOR AIR COOLED CHILLER ROOF SUPPORT DETAIL. REFERENCE TMR400 FOR INSULATED PIPE HOUSING ROOF PENETRATION DETAIL. REFERENCE TMR400 FOR SAFETY VALVE DISCHARGE PIPING DETAIL. PROVIDE SPLIT SYSTEM OUTDOOR UNIT WITH WALL HANGING MOUNTING BRACKET MOUNT APPROXIMATELY 2' ABOVE TOP OF ROOF INSULATION.



1 ROOF PLAN - PIPING
1/8" = 1'-0"

2/14/2025 10:27:23 AM
 2/14/2025 10:27:23 AM
 2/14/2025 10:27:23 AM

Revisions:	Date:

CONSULTANT


IMEG

1800 SOUTH STREET
 SUITE 1000
 SIOUX FALLS, SD 57105
 P 605.336.1111
 WWW.IMEG.COM

ARCHITECT/ENGINEER OF RECORD

ANDERSON

186DS 1st Ave. W. 2120 Plymouth, MN 55441
 P 781.432.4000 | F 781.432.4000 | JAW@A.E.CORP
 Anderson Engineering Co. Minneapolis, MN | PEO # 16064



Office of Construction and Facilities Management
 VA U.S. Department of Veterans Affairs


Drawing Title	ROOF PLAN - PIPING
Approved:	

Phase	BID DOCUMENTS
	FULLY SPRINKLERED

Project Title	CONSTRUCT NEW SPS
Location	Sioux Falls, SD
Issue Date	02/14/2025
Checked	DAVING
Drawn	DELLE

Project Number	438-460
Building Number	5
Drawing Number	MP121

- KEYNOTES:**
1. PRESSURE GAUGE WITH SHUBBER PER SPECIFICATIONS. MOUNT ON WALL STAND OR VIBRATION-FREE PIPE BRACKET ABOVE PUMP. INSTALL FLEXIBLE COPPER TUBING TO PIPING CONNECTIONS TO AVOID VIBRATION DAMAGE TO THE GAUGE. GAUGE SHALL BE OLICVERN FILLED. PREFERRED CONNECTION LOCATIONS ARE: (a) JUST UPSTREAM OF STRAINER & PUMP INLET, (b) GAUGE TAPPING ON PUMP INLET FLANGE, (c) DIFFERENTIAL PRESSURE FLOW SWITCH FURNISHED BY CHILLER MANUFACTURER. FIELD INSTALLED.
 2. REMOVE & RETAIN TEMPORARY STRAINERS FROM SUCTION OFFUSER AT END OF CONSTRUCTION. PROVIDE SUPPORT LEG AS REQUIRED BY MANUFACTURER.
 3. PRESSURE GAUGES SHALL BE OLICVERN FILLED.
 4. REMOVE & RETAIN TEMPORARY STRAINERS FROM SUCTION OFFUSER AT END OF CONSTRUCTION. PROVIDE SUPPORT LEG AS REQUIRED BY MANUFACTURER.
 5. DIFFERENTIAL PRESSURE SENSOR USED TO CONTROL VFD'S. PIPE PER MANUFACTURER'S RECOMMENDATIONS. VERIFY FINAL LOCATION WITH ENGINEER.
 6. CHILLED WATER MAKE-UP WATER METER MONITORED BY BUILDING AUTOMATION SYSTEM.
 7. PROVIDE BURN 'DO NOT SHUT DURING SYSTEM OPERATION' THE NUMBER OF COLLS MAY VARY BETWEEN MANUFACTURERS. CONTRACTOR SHALL SIZE PIPING TO EACH COLL SECTION AT NOT OVER 4 FEET OF PRESSURE DROP PER 100 FEET OF PIPE AND PROVIDE ADDITIONAL UNIONS, VALVES, AND FIT FLUGS AS SHOWN FOR COLLS. ARRANGE PIPING SO COLLS CAN BE REMOVED WITHOUT REMOVING PIPING ABOVE THE UNIONS OR FLANGES. PIPE LOCATION MUST NOT RESTRICT OPENING OF ACCESS DOORS.
 8. PROVIDE COUPON TEST RACK AS INDICATED FOR EACH SYSTEM AS SHOWN.
 9. TRIPLE DUTY OR BALANCING VALVES ARE NOT PERMITTED ON VARIABLE FLOW SYSTEMS. USE VENTURI FOR PUMP FLOW TESTING.



1 AIR COOLED CHILLER FLOW DIAGRAM - VARIABLE PRIMARY
NO SCALE

Revisions: _____ Date: _____ VA FORM 08-0231	CONSULTANT 	ARCHITECT/ENGINEER OF RECORD 	STAMP 	Office of Construction and Facilities Management U.S. Department of Veterans Affairs	Drawing Title: CHILLED WATER FLOW DIAGRAM	Phase: BID DOCUMENTS	Project Title: CONSTRUCT NEW SPS	Project Number: 438-460
					Approved: _____	FULLY SPRINKLERED	Location: Sioux Falls, SD	Building Number: 5 Drawing Number: MP502

RELIEF VALVE SCHEDULE

NOTES:
 1. ASME CODE STAMPED VALVE PROVIDED WITH PIV TO RELIEF MAXIMUM COMBINED CAPACITY OF STATION.
 2. PROVIDE WITH DSRP PLAN BELOW.

TAG NAME	SERVICE	CAPACITY LBS/HR	SET POINT PSIG	INLET SIZE (IN)	OUTLET SIZE (IN)	ORIFICE (IN)	MANUFACTURER	MODEL	NOTES
RV-1	PROV-2A & B	3542	75	2.1/2"	4"	4.3/4"	KUNKLE	8525	NOTES 1 & 2
RV-2	PROV-2A & B	3580	25	2.1/2"	4"	4.3/4"	KUNKLE	8525	NOTES 1 & 2

PRESSURE REDUCING VALVE SCHEDULE

NOTES:
 1. COMPLETE SECTION TO INCLUDE SAFETY VALVE, BYPASS, STEAM TRAPS, ETC. REFER TO STEAM AND CONDENSATE FLOW DIAGRAM FOR ADDITIONAL REQUIREMENTS.
 2. REFER TO SPECIFICATION SECTION 23.21.3 FOR ADDITIONAL INFORMATION.

TAG NAME	SERVICE	LB/HR	INLET PRESSURE (PSI)	OUTLET PRESSURE (PSI)	VALVE SIZE	MANUFACTURER	MODEL	NOTES
PRV-1A	SPS MEDIUM PRESSURE STEAM	3070	100	50	2"	THERMAFO	JVJ	NOTES 1 & 2
PRV-1B	SPS MEDIUM PRESSURE STEAM	3300	100	50	1.1/2"	THERMAFO	JVJ	NOTES 1 & 2
PRV-2A	SPS LOW PRESSURE STEAM	4050	60	15	1.1/2"	THERMAFO	JVJ	NOTES 1 & 2
PRV-2B	SPS MEDIUM PRESSURE STEAM	2550	60	15	1.1/2"	THERMAFO	JVJ	NOTES 1 & 2

HEAT EXCHANGER SCHEDULE - STEAM TO WATER

NOTES:
 1. STEAM PRESSURE INDICATED IS THE PRESSURE AVAILABLE DOWNSTREAM OF THE CONTROL VALVE.
 2. ONE HEAT EXCHANGER IS 100% REDUNDANT.

TAG NAME	SERVICE	WATER W.P.D. (GPM)	HEATING SURFACE (SQ FT)	STEAM (NOTE 1) (PSI)	HEATING SURFACE (SQ FT)	FOULING FACTOR	LENGTH (FT)	DIAMETER (IN)	DRY WT (LBS)	MANUFACTURER	MODEL	NOTES			
HE-1A	HEATING WATER SYSTEM	140.0	0.7	150	180	15	2050	126.0	0.0033	70"	1-10"	1396	TACO	E22208S	NOTE 2
HE-1B	HEATING WATER SYSTEM	140.0	0.7	150	180	15	2050	126.0	0.0033	70"	1-10"	1396	TACO	E22208S	NOTE 2

HEAT EXCHANGER SCHEDULE - PLATE AND FRAME

NOTES:
 1. COLD SIDE PERFORMANCE BASED ON 30% PROPYLENE GLYCOL.
 2. COLD SIDE PERFORMANCE BASED ON 50% PROPYLENE GLYCOL.

TAG NAME	SERVICE	HOT SIDE				COLD SIDE				PLATE SIZE		# OF PLATES	MANUFACTURER	MODEL	NOTES		
		W.P.D. (GPM)	HEAD (FT)	TEMP (°F)	DIFF (°F)	W.P.D. (GPM)	HEAD (FT)	TEMP (°F)	DIFF (°F)	LENGTH (FT)	WIDTH (IN)						
HE-2B	GLYCOL HEATING WATER SYSTEM	75.0	18.2	180.0	150.0	7.5	20.0	20.0	145.0	17.0	33.8	48	34	18	ALFA LAVAL	AD	NOTE 1
HE-3	SNOW MELT SYSTEM	1.0	34.0	180.0	150.0	7.5	20.0	22.0	150.0	11.5	4	30	10	7	ALFA LAVAL	AD	NOTE 2

CONDENSATE RETURN STATION SCHEDULE

1. LB/HR IS ACTUAL MAXIMUM LOAD OF SYSTEM.
 2. PROVIDE WITH GAUGE GLASS, DRAIN THERMOMETER, INLET BASKET STRAINER, DISCHARGE PRESSURE GAUGE, LIFTING EYES, NEMA 1 HIGH LEVEL FLOAT SWITCH, AND SUCTION VALVES.
 3. PROVIDE HARD WIRED CONNECTION TO BAS FOR PUMP FAILURE ALARM.

TAG NAME	SERVICE	CONFIGURATION	LB/HR	CONDENSATE TEMPERATURE (°F)	OPM TOTAL	RECEIVER CAPACITY (GALLONS)	DISCHARGE PRESSURE (PSI)	NO. OF PUMPS	HP	NO. OF POWER CONNECTIONS	VOLTAGE	PHASES	DISCONNECT (NOTE A)	BY TYPE (NOTE A)	BY TYPE (NOTE A)	BY TYPE (NOTE A)	BY TYPE (NOTE A)	SCOR	MANUFACTURER	MODEL	NOTES
CRS-1	SPS LOW PRESSURE STEAM	DUPLX	900	210	22	20	40	2	11.5	2	480 V	3	MFR	NF	MFR	NF	MFR	5000	DOMESTIC PUMP	120CB	NOTES 1, 2, & 3
CRS-2	SPS LOW PRESSURE STEAM	DUPLX	450	210	22	20	40	2	11.5	2	480 V	3	MFR	NF	MFR	NF	MFR	5000	DOMESTIC PUMP	120CB	NOTES 1, 2, & 3

AIR COOLED CHILLER SCHEDULE

NOTES:
 1. SEE SPECIFICATION SECTION 23.14.30 FOR ADDITIONAL REQUIREMENTS.

TAG NAME	SERVICE	REFRIGERANT	CAPACITY PERFORMANCE					EVAPORATOR PERFORMANCE					ELECTRICAL					MAX DIMENSIONS					WEIGHT					VIBRATION ISOLATION									
			DESIGN TONS	STAGES OF UNLOADING	100	75	50	25	NPLV (1)	15.0	16.5	18.0	19.5	21.0	22.5	24.0	25.5	27.0	28.5	30.0	31.5	33.0	34.5	36.0	37.5	39.0	40.5	42.0	43.5	45.0	46.5	48.0	49.5	51.0	52.5	54.0	55.5
ACC-1	STERILE PROCESSING ADDITION	R-32	173.8	6	10.0	14.3	18	19.2	16.5	52	80	346	6.5	0.0011	6	SCROLL	1	480 V	3	350 A	450 A	EC	NF	MFR	PV	65	298"	88"	90"	8978	8978	184	3/4"	DAIKIN APPLIED	AGZ14F	NOTE 1	

GLYCOL FEED SYSTEM

NOTES:
 1. PACKAGE SYSTEM COMPLETE WITH STORAGE TANK, PUMP, AND CONTROLS WITH AUDIBLE AND VISUAL ALARM, DESIGNED TO ADD GLYCOL SOLUTION TO A CLOSED LOOP WATER SYSTEM. SYSTEM SHALL AUTOMATICALLY MAINTAIN PRESSURE IN THE PUMPING SYSTEM.
 2. PROVIDE CUTOFF AND ALARM IN CASES OF LOW LEVELS. HIGH PRESSURE. PROVIDE BYPASS CONTACT FOR ALARM POINT TO DDC.
 3. DISCONNECTS WITH FILLER/STORAGE TANK AND AS MONITOR FLOOR LEVELS. PUMPING ASSEMBLY AND STEEL FRAME WITH LEGS. LEG SHALL BE REMOVABLE FOR FILLING AND PROVIDE MEANS FOR SYSTEM RELIEF VALVE OUTLET TO BE PIPED BACK TO TANK WITHOUT REMOVAL OF PIPING FROM RELIEF VALVE OR AUTOMATIC AIRVENT 4. PUMPING SYSTEM SHALL CONSIST OF A PUMP, STARTER, PRESSURE TANK WITH CONTROL, PRESSURE REDUCING VALVE, SHUTOFF VALVE, AND PRESSURE GAUGE.

TAG NAME	SERVICE	TANK VOLUME (GAL)	PUMP HEAD (FT)	HP	VOLUME (GAL)	PHASES (BY NOTE A)	DISCONNECT (NOTE A)	BY TYPE (NOTE A)	BY TYPE (NOTE A)	BY TYPE (NOTE A)	BY TYPE (NOTE A)	SCOR	MANUFACTURER	MODEL	NOTES
GF-1	ANLT THERMAFO	50.0	15	0.33	100	1	MFR	MFR	5000	WERLESS	OMP	NOTES 1, 2, 3, & 4			
GF-2	SNOW MELT SYSTEM	50.0	15	0.33	100	1	MFR	MFR	5000	WERLESS	OMP	NOTES 1, 2, 3, & 4			

PUMP SCHEDULE

NOTES:
 1. PROVIDE SHAFT GROUNDING AS REQUIRED IN THE MOTOR SPECIFICATION 23.05.13.
 2. PUMP SELECTED FOR 30% PROPYLENE GLYCOL.
 3. PUMP SELECTED FOR 50% PROPYLENE GLYCOL.

TAG NAME	SERVICE	W.P.D. (GPM)	HP	INLET SIZE (IN)	IMPELLER SIZE (IN)	EFFICIENCY (%)	SHIP (IN)	HP (IN)	OPM	VOLTAGE	PHASES	DISCONNECT (NOTE A)	BY TYPE (NOTE A)	BY TYPE (NOTE A)	BY TYPE (NOTE A)	BY TYPE (NOTE A)	SCOR	LENGTH (FT)	WIDTH (IN)	HEIGHT (IN)	WEIGHT (LBS)	TYPE	DEFN	MANUFACTURER	MODEL	NOTES
CWP-1A	CHILLED WATER SYSTEM	275.0	90.0	3"	10.0	73.0	7.0	10	1600	480	3	EC	F	EC	VFD	34.63	14.83	17.25"	297	M3	3/4"	B & G	1510 SERIES	NOTE 1		
CWP-1B	CHILLED WATER SYSTEM	275.0	90.0	3"	10.0	73.0	7.0	10	1600	480	3	EC	F	EC	VFD	34.63	14.83	17.25"	297	M3	3/4"	B & G	1510 SERIES	NOTE 1		
CWP-1A	GLYCOL HEATING WATER SYSTEM	75.0	100.0	48.7"	2"	9.500	3.38	7.5	1600	480	3	EC	F	EC	VFD	34.63	14.83	17.25"	297	M3	3/4"	B & G	1510 SERIES	NOTES 1 & 2		
CWP-1B	GLYCOL HEATING WATER SYSTEM	75.0	100.0	48.7"	2"	9.500	3.38	7.5	1600	480	3	EC	F	EC	VFD	34.63	14.83	17.25"	297	M3	3/4"	B & G	1510 SERIES	NOTES 1 & 2		
OWP-1	SNOW MELT SYSTEM	8.0	80.0	65.3"	1"	4.500	1.5	2	1600	480	3	EC	F	EC	VFD	16"	14"	18"	60	1/2"	3/4"	1.5A	1510 SERIES	NOTE 1		
HWP-1A	HEATING WATER SYSTEM	140.0	80.0	61.5"	2"	9.500	4.45	7.5	1600	480	3	EC	F	EC	VFD	34.63	14.83	17.25"	297	M3	3/4"	B & G	1510 SERIES	NOTE 1		
HWP-1B	HEATING WATER SYSTEM	140.0	80.0	61.5"	2"	9.500	4.45	7.5	1600	480	3	EC	F	EC	VFD	34.63	14.83	17.25"	297	M3	3/4"	B & G	1510 SERIES	NOTE 1		

PIPE INSULATION SCHEDULE (HYDRONIC)

GENERAL NOTES:
 1. REFER TO THE SPECIFICATIONS FOR TYPE DESCRIPTIONS AND JACKETING REQUIREMENTS. VALUES LISTED BELOW ARE BASED ON ASHRAE / IECC REQUIREMENTS.
 2. TYPE A INSULATION IS NOT ALLOWED IN NON-AIR CONDITIONED SPACES (SUCH AS MECHANICAL ROOM, EXTERIOR, ATTICS, ETC) ON PIPE SYSTEMS WITH FLUID TEMPERATURES BELOW 50 DEG F.
 3. TYPE B INSULATION GREATER THAN 1" THICK SHALL BE INSTALLED USING MULTIPLE LAYERS OF 3/4" OR 1" WITH STAGGERED SEAMS.
 4. TYPE B IS NOT ALLOWED IN RETURN AIR PLUMBING, UNLESS LISTED AND LABELED AS 25% RATED PER ASTM E84A.72
 5. TYPE C-1 SHALL BE INSTALLED IN TWO (2) LAYERS WITH STAGGERED SEAMS.
 6. PROVIDE RIGID INSERT AT HANGERS, EITHER PRE-MANUFACTURED COUPLINGS OR TYPE C, D, OHOT PIPE ONLY, E (WHERE ALLOWED BY CODE) OR F INSULATION. SEE SPEC FOR MORE DETAILS.

PIPE SYSTEM	INSULATION TYPE AND THICKNESS FOR NOMINAL PIPE OR TUBE SIZE (DIRECT BURIED)		INSULATION TYPE AND THICKNESS FOR NOMINAL PIPE OR TUBE SIZE (DIRECT BURIED)												NOTES	
	TYPE	THICKNESS (IN)	1" TO 1 1/2"	1 1/2" TO 2"	2" TO 2 1/2"	2 1/2" TO 3"	3" TO 3 1/2"	3 1/2" TO 4"	4" TO 4 1/2"	4 1/2" TO 5"	5" TO 5 1/2"	5 1/2" TO 6"	6" TO 6 1/2"	6 1/2" TO 7"		7" TO 7 1/2"
CWR - CHILLED WATER RETURN	A-2.5	1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5
CWS - CHILLED WATER SUPPLY	A-2.5	1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5
OWR - OUTDOOR WATER RETURN	B-1	1	B-1	B-1	B-1	B-1	B-1	B-1	B-1	B-1	B-1	B-1	B-1	B-1	B-1	B-1
OWS - OUTDOOR WATER SUPPLY	B-1	1	B-1	B-1	B-1	B-1	B-1	B-1	B-1	B-1	B-1	B-1	B-1	B-1	B-1	B-1
HPH - HIGH PRESSURE HEATING WATER RETURN	A-2.5	1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5
HPH - HIGH PRESSURE HEATING WATER SUPPLY	A-2.5	1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5
LR - LOW PRESSURE RETURN	A-2.5	1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5
LR - LOW PRESSURE SUPPLY	A-2.5	1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5
MR - MEDIUM PRESSURE RETURN	A-2.5	1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5
MR - MEDIUM PRESSURE SUPPLY	A-2.5	1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5
CR - CONDENSATE RETURN	A-2.5	1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5
CR - CONDENSATE SUPPLY	A-2.5	1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5	A-1.5

FAN COIL UNIT SCHEDULE - HYDRONIC

NOTES:
 1. PROVIDE FAN COIL UNIT WITH CONDENSATE PUMP.
 2. PROVIDE FAN COIL UNIT WITH WALL MOUNTED THERMOSTAT.
 3. FAN COIL UNIT SHALL BE EXPOSED CEILING HUNG TYPE.
 4. SCHEDULED LOADS ARE MINIMUM CAPACITIES BASED ON ZONE HEATING AND COOLING DEMANDS. FAN COIL UNIT CAPACITIES MAY BE GREATER.
 5. LISTED FLOW RATE IS MAXIMUM FOR BASIS OF DESIGN EQUIPMENT. COORDINATE BALANCE FLOW RATES WITH BALANCING CONTRACTOR BASED ON PERFORMANCE OF FAN COIL UNITS BEING PROVIDED.

TAG NAME	AREA SERVED	EAT		COOLING COOL		HEATING COOL		ELECTRICAL					MAX DIMENSIONS																
		CFM	W.P.D. (GPM)	W.P.D. (GPM)	W.P.D. (GPM)	W.P.D. (GPM)	W.P.D. (GPM)	W.P.D. (GPM)	W.P.D. (GPM)	W.P.D. (GPM)	W.P.D. (GPM)	W.P.D. (GPM)	W.P.D. (GPM)	W.P.D. (GPM)	W.P.D. (GPM)	W.P.D. (GPM)	W.P.D. (GPM)												
FCU-1	MECHANICAL ROOM	500	0.3	100.0	19.3	7.85	3.8	40	52	5.00	26.3	1.8	180	150	3.50	0.25	1800	277	1	MFR	NF	PV	5000	20	31	10	IEC	CXBK8A	NOTES 1, 2, 3, 4, & 5
FCU-2	MECHANICAL ROOM	500	0.3	100.0	19.3	7.85	3.8	40	52	5.00	26.3	1.8	180	150	3.50	0.25	1800	277	1	MFR	NF	PV	5000	20	31	10	IEC	CXBK8A	NOTES 1, 2, 3, 4, & 5
FCU-3	MECHANICAL ROOM	500	0.3	100.0	19.3	7.85	3.8	40	52	5.00	26.3	1.8	180	150	3.50	0.25	1800	277	1	MFR	NF	PV	5000	20	31	10	IEC	CXBK8A	NOTES 1, 2, 3, 4, & 5

SPLIT SYSTEM UNIT SCHEDULE

NOTES:
 1. PROVIDE SPLIT SYSTEM CONDENSING UNIT WITH LOW AMBIENT COOLING KIT.
 2. PROVIDE SPLIT SYSTEM EVAPORATOR WITH CONDENSATE PUMP.


TAG NAME	AREA SERVED	INDOOR UNIT		OUTDOOR UNIT		OUTDOOR UNIT MAX DIMENSIONS					ELECTRICAL													
		COOLING MBH	HEATING MBH	LENGTH (IN)	WIDTH (IN)	HEIGHT (IN)	WEIGHT (LBS)	MODEL	SEER	MOCA	MOCP	VOLTAGE	PHASES	DISCONNECT (NOTE A)	BY TYPE (NOTE A)	BY TYPE (NOTE A)	BY TYPE (NOTE A)	BY TYPE (NOTE A)	SCOR	MANUFACTURER	MODEL	NOTES		
SSR-2	HS ELECTRICAL ROOM	715	21	27.4	41.9	8.5	11.75	27.6	RXSD4	20	30	58	1	3-1/4"	3-1/4"	11-1/4"	185.4	RXSD4	MFR	NF	MFR	5000	SABLING	NOTES 1 & 2
SSR-2	HS ELECTRICAL ROOM	715	21	27.4	41.9	8.5	11.75	27.6	RXSD4	20	30	58	1	3-1/4"	3-1/4"									

GENERAL MECHANICAL NOTES:

1. REFERENCE M200 - MECHANICAL CONTROLS COVER SHEET FOR CONTROLS SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
2. COORDINATE AND CONFIRM ALL ARCHITECTURALLY EXPOSED DEVICE LOCATIONS WITH ARCHITECT PRIOR TO ROUGH-IN OR INSTALLATION.
3. REFERENCE M900 FOR VENTILATION EQUIPMENT SCHEDULES.
4. REFERENCE M900 FOR PIPING EQUIPMENT SCHEDULES.
5. REFERENCE T9000 FOR VARIABLE FREQUENCY DRIVE CONTROL DIAGRAM.
6. REFERENCE S9000 FOR THE NIGHT SETBACK CONTROL SEQUENCE.
7. REFERENCE S9000 FOR TERMINAL AIR BOX REPORT GENERATION SEQUENCE.

KEYNOTES:

PROVIDE DIFFERENTIAL PRESSURE SENSORS AT LOCATIONS INDICATED ON DRAWINGS. DIFFERENTIAL PRESSURE SENSORS ARE INTENDED FOR MONITORING USE ONLY. THEY SHOULD NOT BE USED TO CONTROL EQUIPMENT. A TYPICAL RANGE OF +1.0" W.C. OR SIMILAR, SHOULD BE PROVIDED.



1 GROUND LEVEL FLOOR PLAN - PRESSURIZATION PLAN

24" X 36" (610 X 914) mm
 1/8" = 1'-0" (3.175 mm = 152.4 mm)
 02/14/2025
 10:45:43 AM
 24" X 36" (610 X 914) mm
 1/8" = 1'-0" (3.175 mm = 152.4 mm)
 02/14/2025
 10:45:43 AM

Revisions:	Date:

CONSULTANT

IMEG

1800 13th Street
 Sioux Falls, SD 57105
 605.336.1111
 www.imeg.com


PROJECT # 1908040101

SCALE: AS SHOWN

ARCHITECT/ENGINEER OF RECORD

ANDERSON

186DS 3rd Ave. W. 8120 Rapid City, SD 57105
 P 605.336.4000 | F 605.336.4000 | www.anderson.com
 Anderson Engineering of Architecture, LLC | PEO # 16064



Office of Construction and Facilities Management

VA U.S. Department of Veterans Affairs


Drawing Title	FIRST LEVEL FLOOR PLAN - ROOM PRESSURIZATION PLAN
Approved:	

Phase	BID DOCUMENTS
FULLY SPRINKLERED	

Project Title	CONSTRUCT NEW SPS
Location	Sioux Falls, SD
Issue Date	02/14/2025
Checked	DAVING
Drawn	DELLE

Project Number	438-460
Building Number	5
Drawing Number	MC102

- GENERAL MECHANICAL NOTES:**
1. REFERENCE M2000 - MECHANICAL CONTROLS COVER SHEET FOR CONTROLS SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
 2. COORDINATE AND CONFIRM ALL ARCHITECTURALLY EXPOSED DEVICE LOCATIONS WITH ARCHITECT PRIOR TO ROUGH-IN OR INSTALLATION.
 3. REFERENCE M1900 FOR VENTILATION EQUIPMENT SCHEDULES.
 4. REFERENCE M1900 FOR PIPING EQUIPMENT SCHEDULES.
 5. REFERENCE T14000 FOR VARIABLE FREQUENCY DRIVE CONTROL DIAGRAM.
 6. REFERENCE T14000 FOR THE NIGHT SETBACK CONTROL SEQUENCE.
 7. REFERENCE T14000 FOR TERMINAL AIR BOX REPORT GENERATION SEQUENCE.
- KEYNOTES:**
1. REFERENCE J24000 FOR HEATING WATER CONTROL DIAGRAM.
 2. REFERENCE J24000 FOR SNOW MELT SYSTEM CONTROL DIAGRAM.
 3. REFERENCE S14000 FOR GLYCOL FEED STATION CONTROL DIAGRAM.
 4. REFERENCE S14000 FOR CONDENSATE RETURN PUMP MONITORING CONTROL DIAGRAM.
 5. REFERENCE M1C401 FOR AHU-1 AIR HANDLING UNIT CONTROL DIAGRAM.
 6. REFERENCE M1C402 FOR AHU-2 AIR HANDLING UNIT CONTROL DIAGRAM.
 7. REFERENCE J24000 FOR EXHAUST FAN AHU INTERLOCK CONTROL DIAGRAM.
 8. REFERENCE S14000 FOR FAN COIL UNIT CONTROL DIAGRAM.
 9. REFERENCE S14000 FOR DOMESTIC HOT WATER CONTROL DIAGRAM.
 10. REFERENCE T14000 FOR WATER TREATMENT METERING CONTROL DIAGRAM.
 11. REFERENCE T14000 FOR AIR COMPRESSOR CONTROL DIAGRAM.
 12. REFERENCE T14000 FOR GLYCOL PRE-HEAT LOOP CONTROL DIAGRAM.
 13. REFERENCE T14000 FOR REVERSE OSMOSIS SYSTEM CONTROL DIAGRAM.
 14. REFERENCE J24000 FOR DEIONIZED WATER SYSTEM CONTROL DIAGRAM.




1 INTERSTITIAL/FIRST FLOOR PLAN - CONTROLS
1/8" = 1'-0"

2/14/2025 10:24:55 AM
 2/14/2025 10:24:55 AM
 2/14/2025 10:24:55 AM

Revisions: _____ Date: _____	CONSULTANT 	ARCHITECT/ENGINEER OF RECORD 	STAMP 	Office of Construction and Facilities Management U.S. Department of Veterans Affairs	Drawing Title INTERSTITIAL/FIRST LEVEL FLOOR PLAN - CONTROLS	Phase BID DOCUMENTS	Project Title CONSTRUCT NEW SPS	Project Number 438-460
					Approved:	FULLY SPRINKLERED	Location Sioux Falls, SD	Building Number 5
						Issue Date 02/14/2025	Checked DAVING	Drawn DELLE

- GENERAL MECHANICAL NOTES:**
1. REFERENCE MC200 - MECHANICAL CONTROLS COVER SHEET FOR CONTROLS SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
 2. COORDINATE AND CONFIRM ALL ARCHITECTURALLY EXPOSED DEVICE LOCATIONS WITH ARCHITECT PRIOR TO ROUGH-IN OR INSTALLATION. REFERENCE MV900 FOR VENTILATION EQUIPMENT SCHEDULES.
 3. REFERENCE MP900 FOR PIPING EQUIPMENT SCHEDULES.
 4. REFERENCE DM400 FOR VARIABLE FREQUENCY DRIVE CONTROL DIAGRAM.
 5. REFERENCE DM400 FOR THE NIGHT SETBACK CONTROL SEQUENCE.
 6. REFERENCE DM400 FOR TERMINAL AIR BOX REPORT GENERATION SEQUENCE.
- KEYNOTES:**
- REFERENCE IM400 FOR AIR COOLED CHILLER CONTROL DIAGRAM.
 - REFERENCE JM400 FOR EXHAUST FAN AND INTERLOCK CONTROL DIAGRAM.
 - REFERENCE IM400 FOR CONTINUOUS EXHAUST FAN OPERATION CONTROL DIAGRAM.



1 ROOF PLAN - CONTROLS
1/8" = 1'-0"

2/14/2025 10:20:03 AM
 2/14/2025 10:20:03 AM
 2/14/2025 10:20:03 AM

Revisions:	Date:

CONSULTANT

IMEG

1805 SOUTH STREET
 SUITE 1000
 11200 W. 112TH AVE., SUITE 1000
 WASHINGTON, NE 68441
 PHONE: (402) 486-1100
 FAX: (402) 486-1101
 WWW.IMEG.COM


PROJECT # 1805000000

SCALE: AS SHOWN

ARCHITECT/ENGINEER OF RECORD

ANDERSON

1860S 1st Ave. W. 8100 Plymouth, MN 55441
 P 788.432.4000 | F 788.432.4000 | anderson.com
 Anderson Engineering of Minnesota, LLC | PEO # 16064



Office of Construction and Facilities Management

VA U.S. Department of Veterans Affairs

Drawing Title: **ROOF PLAN - CONTROLS**

Approved: _____

Phase: **BID DOCUMENTS**

FULLY SPRINKLERED

Project Title: **CONSTRUCT NEW SPS**

Project Number: **438-460**

Building Number: **5**




Location: **Sioux Falls, SD**

Issue Date: **02/14/2025**


Checked: **DAVING**

Drawn: **DELLE**


Drawing Number: **MC121**




1 AIR COOLED CHILLER CONTROLS - VARIABLE PRIMARY




2 HEATING WATER CONTROL DIAGRAM



5 GLYCOL FEED STATION CONTROL DIAGRAM




3 GLYCOL PREHEAT LOOP CONTROL




4 SNOW MELT SYSTEM CONTROL




6 CONDENSATE RETURN PUMP MONITORING CONTROL



7 VARIABLE FREQUENCY DRIVE CONTROL



CONSULTANT IMEG 1800 W. 10TH STREET, SUITE 100 DENVER, CO 80202 TEL: 303.733.1111 FAX: 303.733.1112 WWW.IMEG.COM		ARCHITECT/ENGINEER OF RECORD ANDERSON 18605 9th Ave., B. 2150 Platteau, MR 26441 783.432.0800 P 788.432.6900 J 888.432.0800 Anderson Engineering Co. 18605 9th Ave., B. 2150 Platteau, MR 26441		Office of Construction and Facilities Management U.S. Department of Veterans Affairs	Drawing Title: CONTROL DIAGRAMS Approved:	Phase: BID DOCUMENTS Fully Sprinklered	Project Title: CONSTRUCT NEW SPS Project Number: 438-460 Bidding Number: 5 Drawing Number: MC400
Revisions:	Date:	Project Location: Sioux Falls, SD Issue Date: 02/14/2025 Checked: DAVING Drawn: DELLE					



SEQUENCE OF OPERATION

WHEN AHU IS INDICED TO RUN, THE FOLLOWING SHALL OCCUR:

- SMOKE DAMPERS AND COMBINATION FIRE/SMOKE DAMPERS SHALL OPEN.
- AFTER A 30 SECOND DELAY (ADJ.) TO ALLOW FOR OPENING OF SMOKE DAMPERS AND COMBINATION FIRE/SMOKE DAMPERS, SUPPLY FAN SHALL BE ENABLED TO RUN.
- WHEN THE SUPPLY FAN HAS STARTED THE INTERLOCKED EXHAUST FANS SHALL START AS SHOWN IN THE FAN INTERLOCK SCHEDULE.

SEQUENCE OPERATIONS:

- FMS SHALL MODULATE SIGNAL TO SUPPLY FAN VFD TO MAINTAIN DUCT STATIC PRESSURE AS MEASURED BY STATIC PRESSURE TRANSMITTER NEAR THE END OF THE CRITICAL DUCT BRANCH.
- STATIC PRESSURE RESET:
 - FMS SHALL RESET SUPPLY DUCT STATIC PRESSURE SETPOINT BELOW THE MAXIMUM SETPOINT AS REQUIRED TO MAINTAIN AT LEAST ONE SUPPLY TAB DAMPER 80% (ADJ.) OPEN. FMS SHALL MONITOR ALL SUPPLY TERMINAL AIR BOX POSITIONS TO RESET THE SUPPLY DUCT DIFFERENTIAL STATIC PRESSURE.
- DISCHARGE AIR TEMPERATURE SET POINT:**
 - DISCHARGE AIR SET POINT SHALL BE 60°F (ADJ.)
- DISCHARGE AIR TEMPERATURE RESET:**
 - RESET DISCHARGE AIR TEMPERATURE BASED ON THE ZONE WITH THE GREATEST CALL FOR COOLING. RESET THE TEMPERATURE AS FOLLOWS:
 - WHEN WORST CASE TAB IS LESS THAN 80% (ADJ.) OPEN FOR TEN MINUTES (ADJ.) THEN THE DISCHARGE AIR TEMPERATURE SHALL INCREASE BY 1°F (ADJ.). THIS SHALL CONTINUE UNTIL AHU MAXIMUM DISCHARGE AIR TEMPERATURE OF 60°F (ADJ.) IS ACHIEVED.
 - WHEN WORST CASE TAB IS MORE THAN 80% OPEN FOR TEN MINUTES (ADJ.) THEN THE DISCHARGE AIR TEMPERATURE SHALL DROP BY 1°F (ADJ.). THIS SHALL CONTINUE UNTIL AHU MINIMUM DISCHARGE AIR TEMPERATURE OF 50°F (ADJ.) IS ACHIEVED.
 - THE MAXIMUM ALLOWABLE SUPPLY AIR DEWPOINT SETPOINT SHALL BE 46.2°F (ADJ.) IF RETURN AIR HUMIDITY IS GREATER THAN SETPOINT. RESET DISCHARGE AIR TEMPERATURE TO 50°F UNTIL SUPPLY AIR DEWPOINT IS 9% LESS THAN MAXIMUM SETPOINT FOR 10 MINUTES (ADJ.)
- STATIC PRESSURE AND DISCHARGE AIR TEMPERATURE RESET PRIORITY:
 - RESET THE DISCHARGE AIR TEMPERATURE PRIOR TO RESETTING THE DUCTWORK STATIC PRESSURE SETPOINT. ONCE THE MAXIMUM SUPPLY TEMPERATURE IS REACHED THEN THE SYSTEM SHALL ENABLE THE STATIC PRESSURE RESET.
- VENTILATION LINE CONTROL:**
 - WHENEVER THE AIR HANDLING UNIT IS IN OCCUPIED MODE, THE OUTSIDE AIR DAMPER SHALL BE FULLY OPEN.
- COOLING COIL OPERATION:**
 - FMS SHALL MODULATE CHILLED WATER CONTROL VALVE AS REQUIRED TO MAINTAIN DISCHARGE AIR TEMPERATURE SET POINT.
- PREHEAT COIL OPERATION:**
 - PREHEAT COIL CONTROLS SHALL BE ENABLED WHEN OUTSIDE AIR TEMPERATURE DROPS BELOW 45°F (ADJ.). PREHEAT COIL CONTROLS SHALL BE DISABLED WHEN OUTSIDE AIR TEMP RISES ABOVE 45°F (ADJ.).
- FMS SHALL MODULATE HEATING WATER CONTROL VALVE AS REQUIRED TO MAINTAIN DISCHARGE AIR TEMPERATURE SET POINT.
- HUMIDIFIER CONTROL:**
 - HUMIDIFIER CONTROL AND ALARMS SHALL BE ENABLED WHEN OUTSIDE AIR TEMPERATURE DROPS BELOW 45°F (ADJ.) AT WHICH POINT THE ISOLATION STEAM VALVE SHALL FULLY OPEN. HUMIDIFIER CONTROLS AND ALARMS SHALL BE DISABLED WHEN OUTSIDE AIR TEMPERATURE RISES ABOVE 45°F (ADJ.) AT WHICH POINT THE ISOLATION STEAM VALVE SHALL FULLY CLOSE.
- WHEN HUMIDIFIER CONTROLS ARE ENABLED, FMS CONTROLLER SHALL MODULATE STEAM VALVE AS REQUIRED TO MAINTAIN 43°F DEWPOINT (ADJ.) IN THE SUPPLY AIR DUCT. DUCT MOUNTED HUMIDITY TRANSMITTER AT FAN DISCHARGE SHALL PREVENT SUPPLY AIR RELATIVE HUMIDITY FROM EXCEEDING 80% (ADJ.)
- ALARMS, INTERLOCKS AND SAFETIES:**
 - WHEN THE ALARM CONTROL PANEL INDICATES AN ALARM CONDITION, AHU SHALL BE SHUTDOWN.
 - THE FOLLOWING CONDITIONS SHALL SHUTDOWN THE AHU AND SHALL INDICATE AN ALARM CONDITION AT THE FMS WORKSTATION:
 - HIGH STATIC PRESSURE SWITCH INDICATES SUPPLY DUCT STATIC PRESSURE GREATER THAN THE SPECIFIED DUCT PRESSURE CLASS.
 - SHOULD ANY ONE FOOT SECTION OF THE MANUAL RESET LOW LIMIT TEMPERATURE SWITCH BY SENSE AIR TEMP >44°F (ADJ.) IF MULTIPLE FREEZE STATS ARE REQUIRED, WIRE ALL TO A COMMON RESET SWITCH.
 - THE FOLLOWING CONDITIONS SHALL INDICATE AN ALARM AT THE FMS; HOWEVER AHU SHALL CONTINUE TO OPERATE:
 - HEATING COIL CIRCULATION PUMP IS COMMANDED TO RUN AND CURRENT RELAY INDICATES INSUFFICIENT CURRENT FLOW.
 - AN ALARM IS INDICATED AT ANY SUPPLY FAN VFD.
 - DIFFERENTIAL PRESSURE SWITCH ACROSS PRE-FILTER BANK EXCEEDS 0.8 INCHES W.G. (ADJ.)
 - DIFFERENTIAL PRESSURE SWITCH ACROSS POST-FILTER BANK EXCEEDS 1.0 INCHES W.G. (ADJ.)
 - THE TOTAL DIFFERENTIAL PRESSURE ACROSS ALL FILTER BANKS EXCEEDS 2.0 INCHES W.G. (ADJ.)
 - RELATIVE HUMIDITY OF SUPPLY AIR EXCEEDS 80% (ADJ.) AS MEASURED BY DUCT MOUNTED HUMIDITY SWITCH. WHEN HUMIDITY SWITCH TRIPS, STEAM CONTROL VALVE SHALL FULLY CLOSE UNTIL ALARM IS RESET AT FMS WORKSTATION. AN ALARM SHALL NOT INDICATE AT THE FMS WORKSTATION UNLESS HUMIDIFIER CONTROLS ARE ENABLED.
 - WHEN DUCTWORK SUPPLY AIR HUMIDITY EXCEEDS 80% (ADJ.) A SEPARATE DUCT MOUNTED HUMIDITY SWITCH (MANUAL RESET) SHALL DISABLE HUMIDIFIER CONTROLS AND SHALL FULLY CLOSE STEAM ISOLATION VALVE. AN IDENTIFIABLE ALARM CONDITION SHALL BE DISPLAYED AT THE OPERATOR WORKSTATION.
 - SEND AN ALARM TO THE FMS OPERATOR INTERFACE IF THE DISCHARGE AIR TEMPERATURE IS MORE THAN 5°F (ADJ.) ABOVE OR BELOW SETPOINT.
 - IF THE EVENT SUPPLY FAN IS NOT RUNNING (AS INDICATED BY THE CURRENT SENSING RELAYS) RETURN AIR FAN SHALL BE DE-ENERGIZED.
 - WHENEVER AHU IS SHUTDOWN THE FOLLOWING SHALL OCCUR:
 - THE OUTSIDE AIR DAMPER EXHAUST AIR DAMPER SHALL FULLY CLOSE.
 - RETURN AIR DAMPER SHALL FULLY OPEN.
 - PREHEAT COIL HEATING WATER CIRCULATION PUMP AND HEATING WATER CONTROL VALVE SHALL REMAIN UNDER CONTROL OF ITS INPUT SENSOR.
 - ALL SMOKE DAMPERS AND COMBINATION FIRE/SMOKE DAMPERS SHALL FULLY CLOSE.
 - CHILLED WATER CONTROL VALVE SHALL FULLY CLOSE.
 - ISOLATION STEAM VALVE SHALL FULLY CLOSE.
 - SUPPLY FAN AND EXHAUST FAN VFD SHALL BE DE-ENERGIZED.
 - INTERLOCKED EXHAUST FANS SHALL BE DE-ENERGIZED.
- GRAPHICAL DISPLAY:**
 - DISPLAY THE GLOBAL OUTSIDE AIR TEMPERATURE AND HUMIDITY ON AHU GRAPHIC PAGE.


AHU REPORT GENERATION:

DCS/FMS SHALL MONITOR THE FOLLOWING POINTS ON 10 MINUTE (ADJ.) INTERVALS WITHIN A SINGLE TEND. THE TEND SHALL RUN FOR A 100-DAY (ADJ.) DURATION AT WHICH POINT THE NEWEST VALUES SHALL AUTOMATICALLY OVERWRITE THE OLDEST VALUES:

- DATE
- TIME
- GLOBAL OUTSIDE AIR TEMP (°F)
- GLOBAL OUTSIDE AIR HUMIDITY (RH%)
- SUPPLY AIRFLOW (CFM)
- SUPPLY AIR TEMP (SAT) (°F)
- SUPPLY AIR TEMP SETPOINT (°F)
- SUPPLY AIR RELATIVE HUMIDITY (%)
- SUPPLY AIR DEWPOINT (°F)
- OUTSIDE AIRFLOW (CFM)
- OUTSIDE AIRFLOW (CFM)
- PREHEAT COIL DISCHARGE AIR TEMP (°F)
- PREHEAT COIL DISCHARGE AIR TEMP (°F)
- PREHEAT ALARM (STATUS)
- FINAL FILTER ALARM (STATUS)
- GLYCOL HEATING WATER VALVE POSITION (% OPEN)
- GLYCOL HEATING WATER PUMP (ON/OFF)
- CHILLED WATER VALVE POSITION (% OPEN)
- HUMIDIFIER VALVE POSITION (% OPEN)
- HUMIDIFIER ISOLATION VALVE (ENVELOPED)
- SUPPLY DUCT STATIC PRESSURE SETPOINT (INCHES W.G.)
- SUPPLY DUCT STATIC PRESSURE (INCHES W.G.)
- SUPPLY FAN VFD OUTPUT R.F.L. SPEED
- OUTSIDE AIR DAMPER POSITION (OPEN/CLOSE)

THIS INFORMATION SHALL BE ACCESSIBLE TO VIEW IN GRAPHICAL FORM ON THE FMS OPERATOR WORKSTATION.

ONCE PER MONTH THE DCS/FMS SHALL RECORD THE LARGEST AHU AIRFLOW WHICH OCCURRED DURING THAT MONTH, THE DATE, TIME, OUTSIDE AIR TEMP (AND ALL OTHER VALUES LISTED ABOVE) THAT COINCIDE WITH THAT EVENT SHALL ALSO BE RECORDED. THIS INFORMATION SHALL BE STORED TO A MEMORY LOCATION ON THE FMS OPERATOR WORKSTATION THAT IS MAINTAINED (NOT AUTOMATICALLY OVERRITTEN).



1 AIR HANDLING UNIT CONTROL - AHU-1
NO SCALE



CONSULTANT 		ARCHITECT/ENGINEER OF RECORD 		STAMP 	Office of Construction and Facilities Management 	Drawing Title CONTROL DIAGRAMS	Phase BID DOCUMENTS	Project Title CONSTRUCT NEW SPS	Project Number 438-460
Revisions:		Date:		Approved:		Approved:	Checked: DAVING	Drawn: DELLE	Building Number 5
Revisions:		Date:		Approved:		Approved:	Checked: DAVING	Drawn: DELLE	Drawing Number MC401

RETURN FAN AIRFLOW SCHEDULE				
SYSTEM	SUPPLY CFM	EXHAUST FANS	PRESSURIZATION CFM	REMARKS
AHU-2	5,000	EF-3 & EF-4	250	NOTES 1,2,3

- NOTES:**
- RETURN FAN AIRFLOW SETPOINT SHALL BE THE SUPPLY FAN AIRFLOW (AS MEASURED BY THE AHU) MINUS THE SUM OF THE EXHAUST FAN AIRFLOW PLUS THE PRESSURIZATION CFM.
 - FMS SHALL DETERMINE THE OPERATIONAL STATUS OF EACH EXHAUST FAN VIA THE CURRENT SENSING RELAY TO DETERMINE WHETHER THE CFM ASSOCIATED WITH THAT FAN SHOULD BE INCLUDED IN THE RETURN FAN AIRFLOW CALCULATION.
 - SMALLEST FAN AIRFLOW SHALL NOT BE THE CFM INDICATED ON THE FAN SCHEDULE, BUT SHALL BE THE AIRFLOW INDICATED IN THE FINAL TAB REPORT.

FAN INTERLOCK SCHEDULE		
SYSTEM	INTERLOCKED EXHAUST FANS	REMARKS
AHU-1	EF-3 & EF-4	NOTE 1

- NOTES:**
- INTERLOCK EXHAUST FAN OPERATION THROUGH THE FMS WITH RESPECTIVE AHU IN ACCORDANCE WITH AHU SEQUENCE OF OPERATION.



SEQUENCE OF OPERATION:

WHEN AHU/RTU IS SCHEDULED TO RUN, THE FOLLOWING SHALL OCCUR:

- SMOKE DAMPERS AND COMBINATION FIRE/SMOKE DAMPERS SHALL OPEN.
- AFTER A 30 SECOND DELAY (ADJ.) TO ALLOW FOR OPENING OF SMOKE DAMPERS AND COMBINATION FIRE/SMOKE DAMPERS, SUPPLY FAN SHALL BE ENABLED TO RUN.
- WHEN THE SUPPLY FAN HAS STARTED THE RETURN FAN AND INTERLOCKED EXHAUST FANS SHALL START AS SHOWN IN THE FAN INTERLOCK SCHEDULE.

SUPPLY FAN OPERATION:

FMS SHALL MODULATE SIGNAL TO SUPPLY FAN VFD TO MAINTAIN DUCT STATIC PRESSURE AS MEASURED BY STATIC PRESSURE TRANSMITTER NEAR THE END OF THE CRITICAL DUCT BRANCH.

RETURN FAN OPERATION:

RETURN FAN SHALL BE INDEXED TO RUN WHENEVER THE SUPPLY FAN IS INDEXED TO RUN. FMS SHALL MODULATE SIGNAL TO RETURN FAN VFD AS REQUIRED TO MAINTAIN THE AIRFLOW OFFSET AS INDICATED IN THE RETURN FAN AIRFLOW SCHEDULE.

STATIC PRESSURE RESET:

FMS SHALL RESET SUPPLY DUCT STATIC PRESSURE SETPOINT BELOW THE MAXIMUM SETPOINT AS REQUIRED TO MAINTAIN AT LEAST ONE SUPPLY TAB DAMPER 80% (ADJ.) OPEN. FMS SHALL MONITOR ALL SUPPLY TERMINAL AIR BOX POSITIONS TO RESET THE SUPPLY DUCT DIFFERENTIAL STATIC PRESSURE.

DISCHARGE AIR TEMPERATURE SET POINT:

DISCHARGE AIR SET POINT SHALL BE 50°F (ADJ.).

DISCHARGE AIR TEMPERATURE RESET:

RESET DISCHARGE AIR TEMPERATURE BASED ON THE ZONE WITH THE GREATEST CALL FOR COOLING. RESET THE TEMPERATURE AS FOLLOWS:

- WHEN WORST CASE TAB IS LESS THAN 50% (ADJ.) OPEN FOR TEN MINUTES (ADJ.) THEN THE DISCHARGE AIR TEMPERATURE SHALL INCREASE BY 1°F (ADJ.). THIS SHALL CONTINUE UNTIL AHU MAXIMUM DISCHARGE AIR TEMPERATURE OF 60°F (ADJ.) IS ACHIEVED.
- WHEN WORST CASE TAB IS MORE THAN 50% OPEN FOR TEN MINUTES (ADJ.) THEN THE DISCHARGE AIR TEMPERATURE SHALL DROP BY 1°F (ADJ.). THIS SHALL CONTINUE UNTIL AHU MINIMUM DISCHARGE AIR TEMPERATURE OF 50°F (ADJ.) IS ACHIEVED.
- THE MAXIMUM ALLOWABLE RETURN AIR HUMIDITY SETPOINT SHALL BE 60% (ADJ.). IF RETURN AIR HUMIDITY IS GREATER THAN SETPOINT, RESET DISCHARGE AIR TEMPERATURE TO 50°F (ADJ.) UNTIL RETURN AIR HUMIDITY IS 5% LESS THAN MAXIMUM SETPOINT FOR 10 MINUTES (ADJ.).

STATIC PRESSURE AND DISCHARGE AIR TEMPERATURE RESET PRIORITY:

RESET THE DISCHARGE AIR TEMPERATURE PRIOR TO RESETTING THE DUCTWORK STATIC PRESSURE SETPOINT. ONCE THE MAXIMUM SUPPLY TEMPERATURE IS REACHED THIS SYSTEM SHALL ENABLE THE STATIC PRESSURE RESET.

VENTILATION AIR CONTROL:

WHEN IN MANUAL MODE, RETURN AIR DAMPER SHALL BE FULLY OPEN, THE RETURN AIR AND RELIEF AIR DAMPER SHALL MODULATE IN OPPOSITION TO MAINTAIN THE MINIMUM OUTSIDE AIR FLOW RATE, OR TO SATISFY THE ECONOMIZER DISCHARGE AIR SEQUENCE.

COOLING AND COIL OPERATION:

WHEN IN MANU/OUTSIDE AIR MODE, FMS SHALL MODULATE CHILLED WATER CONTROL VALVE AS REQUIRED TO MAINTAIN DISCHARGE AIR TEMPERATURE SET POINT.

WHEN IN ECONOMIZER MODE, FMS SHALL NOT MODULATE COOLING CONTROL VALVE UNLESS RETURN AIR DAMPER IS 5% (ADJ.) OPEN AND RELIEF AIR DAMPER IS 85% (ADJ.) OPEN.

PREHEAT COIL OPERATION:

PREHEAT COIL CONTROLS SHALL BE ENABLED WHEN OUTSIDE AIR TEMP DROPS BELOW 50°F (ADJ.). PREHEAT COIL CONTROLS SHALL BE DISABLED WHEN OUTSIDE AIR TEMP RISES ABOVE 54°F (ADJ.).

FMS SHALL MODULATE HEATING WATER CONTROL VALVE AS REQUIRED TO MAINTAIN DISCHARGE AIR TEMPERATURE SET POINT.

ECONOMIZER OPERATION:

WHEN THE OUTSIDE AIR DRY BULB TEMPERATURE IS LESS THAN THE RETURN AIR DRY BULB TEMPERATURE THE FMS SHALL ENABLE ECONOMIZER CONTROLS. WHEN OUTSIDE AIR DRY BULB TEMPERATURE IS GREATER THAN THE RETURN AIR DRY BULB TEMPERATURE FOR 10 MINUTES THE FMS SHALL DISABLE ECONOMIZER CONTROLS AND SHALL RETURN THE UNIT TO MINIMUM OUTSIDE AIR MODE. ONCE ECONOMIZER CONTROLS HAVE BEEN ENABLED OR DISABLED, THE UNIT SHALL CONTINUE TO OPERATE IN THAT MODE FOR A MINIMUM OF 10 MINUTES (ADJ.) BEFORE BEING ALLOWED TO SWITCH BACK (TO PREVENT SHORT CYCLING).

IN ECONOMIZER MODE THE FMS SHALL MODULATE THE RETURN AND RELIEF DAMPERS AS REQUIRED TO MAINTAIN DISCHARGE AIR TEMPERATURE SETPOINT.

HUMIDIFIER CONTROLS:

HUMIDIFIER CONTROLS AND ALARMS SHALL BE ENABLED WHEN OUTSIDE AIR TEMPERATURE DROPS BELOW 40°F (ADJ.) AT WHICH POINT THE ISOLATION STEAM VALVE SHALL FULLY OPEN. HUMIDIFIER CONTROLS AND ALARMS SHALL BE DISABLED WHEN OUTSIDE AIR TEMPERATURE RISES ABOVE 47°F (ADJ.) FOR 10 MINUTES (ADJ.) AT WHICH POINT THE ISOLATION STEAM VALVE SHALL FULLY CLOSE.

WHEN HUMIDIFIER CONTROLS ARE ENABLED, FMS CONTROLLER SHALL MODULATE STEAM VALVE AS REQUIRED TO MAINTAIN 47°F DEWPOINT (ADJ.) IN THE SUPPLY AIR DUCT. DUCT MOUNTED HUMIDITY TRANSMITTER AT FAN DISCHARGE SHALL PREVENT SUPPLY AIR RELATIVE HUMIDITY FROM EXCEEDING 90% (ADJ.).

SEQUENCE OF OPERATION (CONT.)

ALARMS, INTERLOCKS AND SAFETIES:

WHEN FIRE ALARM CONTROL PANEL INDICATES AN ALARM CONDITION, AHU SHALL BE SHUTDOWN.

THE FOLLOWING CONDITIONS SHALL SHUTDOWN THE AHU AND SHALL INDICATE AN ALARM CONDITION AT THE FMS WORKSTATION:

- LOW STATIC PRESSURE SWITCH INDICATES RETURN DUCT PRESSURE LESS THAN THE SPECIFIED DUCT PRESSURE CLASS.
- LOW STATIC PRESSURE SWITCH INDICATES MIXED AIR PRESSURE LESS THAN THE SPECIFIED DUCT PRESSURE CLASS OF THE OUTSIDE AIR DUCTWORK.
- HIGH STATIC PRESSURE SWITCH INDICATES SUPPLY DUCT STATIC PRESSURE GREATER THAN THE SPECIFIED DUCT PRESSURE CLASS.
- SHOULD ANY ONE FOOT SECTION OF THE MANUAL RESET LOW LIMIT TEMPERATURE SWITCH #1 SENSE AIR TEMP <34°F (ADJ.), IF MULTIPLE FREEZE STATS ARE REQUIRED WIRE ALL TO A COMMON RESET SWITCH.

THE FOLLOWING CONDITIONS SHALL INDICATE AN ALARM AT THE FMS, HOWEVER AHU SHALL CONTINUE TO OPERATE:

- HEATING COIL CIRCULATION PUMP IS COMMAND TO RUN AND CURRENT RELAY INDICATES INCOMPLETE CURRENT FLOW.
- AN ALARM IS INDICATED AT ANY SUPPLY FAN VFD OR RETURN FAN VFD.
- DIFFERENTIAL PRESSURE SWITCH ACROSS PRE-FILTER BANK EXCEEDS 2.0 INCHES W.G. (ADJ.).
- THE TOTAL DIFFERENTIAL PRESSURE ACROSS ALL FILTER BANKS EXCEEDS 2.0 INCHES W.G. (ADJ.).
- RELATIVE HUMIDITY OF SUPPLY AIR EXCEEDS 90% (ADJ.) AS MEASURED BY AUTOMATIC RESET HUMIDITY SWITCH. STEAM HUMIDIFIER CONTROL VALVE SHALL FULLY CLOSE UNTIL ALARM #2 RESET AT FMS WORKSTATION. AN ALARM SHALL NOT INDICATE AT THE FMS WORKSTATION UNLESS HUMIDIFIER CONTROL VALVE IS SHUT OFF.
- WHEN DUCTWORK SUPPLY AIR HUMIDITY EXCEEDS 90%, A SEPARATE DUCT MOUNTED HUMIDITY SWITCH (MANUAL RESET) SHALL DISABLE HUMIDIFIER CONTROLS AND SHALL FULLY CLOSE STEAM ISOLATION VALVE. AN IDENTIFIABLE ALARM CONDITION SHALL BE DISPLAYED AT THE OPERATOR WORKSTATION.
- SHOULD ANY ONE FOOT SECTION OF THE AUTO RESET LOW LIMIT TEMPERATURE SWITCH #2 SENSE AIR TEMPERATURE <38°F (ADJ.) THE FOLLOWING SHALL OCCUR:
 - THE OUTSIDE AIR AND RELIEF DAMPERS SHALL FULLY CLOSE.
 - THIS ACTION SHALL OCCUR INDEPENDENT OF THE FMS AHU CONTROLLER. ONCE THE LOW LIMIT TEMPERATURE SWITCH #2 AIR TEMPERATURE RISES ABOVE SET POINT, OPERATION OF THE OUTSIDE AIR, RELIEF AIR, AND RETURN AIR DAMPERS SHALL BE RESTORED. HOWEVER, THE ALARM SHALL CONTINUE UNTIL ACKNOWLEDGED AND MANUALLY RESET BY THE FMS OPERATOR.
 - SEND AN ALARM TO THE FMS OPERATOR INTERFACED IF THE DISCHARGE AIR TEMPERATURE IS MORE THAN 5°F (ADJ.) ABOVE OR BELOW SETPOINT.

IN THE EVENT SUPPLY FAN IS NOT RUNNING (AS INDICATED BY THE CURRENT SENSING RELAYS) RETURN AIR FAN SHALL BE DE-ENERGIZED.

WHENEVER AHU/RTU IS SHUTDOWN THE FOLLOWING SHALL OCCUR:

- THE OUTSIDE AIR DAMPER AND RELIEF AIR DAMPER SHALL FULLY CLOSE.
- RETURN AIR DAMPER SHALL FULLY OPEN.
- PREHEAT COIL HEATING WATER CIRCULATION PUMP AND HEATING WATER CONTROL VALVE SHALL REMAIN UNDER CONTROL OF ITS INPUT SENSOR.
- CHILLED WATER CONTROL VALVE SHALL FULLY CLOSE.
- ISOLATION STEAM VALVE SHALL FULLY CLOSE.
- SUPPLY FAN AND RETURN FAN VFDs SHALL BE DE-ENERGIZED.
- INTERLOCKED EXHAUST FANS SHALL BE DE-ENERGIZED.

UNOCCUPIED MODE:

PROVIDE TIME OF DAY SCHEDULE TO ALLOW AHU TO ENTER UNOCCUPIED MODE PER SCHEDULE. COORDINATE SCHEDULE WITH OWNER.

- THE SUPPLY AND RETURN FANS SHALL CONTINUE RUNNING, WHEN USING CONSTANT VOLUME OFFSET FOR RETURN AIR FAN CONTROL, THE OFFSET SHALL GO TO ZERO AND THE SUPPLY FAN SHALL BE LIMITED TO THE MAXIMUM RETURN FAN AIR FLOW.
- THE OUTSIDE AIR AND RELIEF AIR DAMPERS SHALL CLOSE AND THE RETURN AIR DAMPER SHALL OPEN. ECONOMIZER CYCLE SHALL TAKE PRECEDENCE OVER DAMPER POSITION.
- ALL SPACE TEMPERATURES SHALL BE ALLOWED TO VARY +/- 10°F (ADJ.) FROM OCCUPIED SETPOINT.

HEATING OPTIMUM START-UP:

- THIS CYCLE SHALL OVERRIDE THE UNOCCUPIED CYCLE IF THE SYSTEM WAS OPERATING AS A RESULT OF THE UNOCCUPIED CYCLE. THE SYSTEM SHALL CONTINUE TO OPERATE. THE DDC SYSTEM SHALL DETERMINE THE MINIMUM RUNTIME TO WARM THE SPACES TO THEIR SETPOINT WHEN THE COMPUTED START TIME IS REACHED. THE AIR HANDLING UNIT DISCHARGE AIR TEMPERATURE SHALL BE MAINTAINED AT A SETPOINT OF 59°F (ADJ.). THE SYSTEM SHALL CONTINUE TO OPERATE IN THIS MODE UNTIL ALL TEMPERATURES EXCEED A SETPOINT OF 69°F (ADJ.) AT THAT TIME, THE DDC SYSTEM SHALL SWITCH TO OCCUPIED CONTROL.

COOLING OPTIMUM START-UP:

- THIS CYCLE SHALL OVERRIDE THE UNOCCUPIED CYCLE IF THE SYSTEM WAS OPERATING AS A RESULT OF THE UNOCCUPIED CYCLE. THE SYSTEM SHALL CONTINUE TO OPERATE. THE DDC SYSTEM SHALL DETERMINE THE MINIMUM RUNTIME TO COOL THE SPACES TO THEIR SETPOINT WHEN THE COMPUTED START TIME IS REACHED. THE AIR HANDLING UNIT DISCHARGE AIR TEMPERATURE SHALL BE MAINTAINED AT A SETPOINT OF 59°F (ADJ.). THE SYSTEM SHALL CONTINUE TO OPERATE IN THIS MODE UNTIL ALL TEMPERATURES ARE LESS THAN A SETPOINT OF 79°F (ADJ.) AT THAT TIME, THE DDC SYSTEM SHALL SWITCH TO OCCUPIED CONTROL.

GENERAL DISPLAY:

DISPLAY THE GLOBAL OUTSIDE AIR TEMPERATURE AND HUMIDITY ON AHU GRAPHIC PAGE.

AHU REPORT GENERATION:

DDC FMS SHALL MONITOR THE FOLLOWING POINTS ON 10 MINUTE (ADJ.) INTERVALS WITHIN A SINGLE TRIP. THE TRIP SHALL RUN FOR A 10 DAY (ADJ.) DURATION AT WHICH POINT THE NEWEST VALUES SHALL AUTOMATICALLY OVERTWRITE THE OLDEST VALUES.

- DATE
- TIME
- GLOBAL OUTSIDE AIR TEMP (°F)
- GLOBAL OUTSIDE AIR DOWNPOT (°F)
- GLOBAL OUTSIDE AIR HUMIDITY (RH%)
- SUPPLY AIR FLOW (CFM)
- SUPPLY AIR TEMP (SAT) (°F)
- SUPPLY AIR TEMP SETPOINT (°F)
- SUPPLY AIR RELATIVE HUMIDITY (%)
- DISCHARGE AIR DOWNPOT (°F)
- RETURN AIRFLOW (CFM)
- RETURN AIR TEMP (SAT) (°F)
- RETURN AIR RELATIVE HUMIDITY (%)
- OUTSIDE AIRFLOW (°F)
- MIXED AIR TEMP (°F)
- PREHEAT COIL DISCHARGE AIR TEMP (°F)
- PRE-FILTER ALARM STATUS
- HEATING WATER VALVE POSITION (% OPEN)
- CHILLED WATER VALVE POSITION (% OPEN)
- HUMIDIFIER VALVE POSITION (% OPEN)
- HUMIDIFIER ISOLATION VALVE (OPEN/CLOSE)
- SUPPLY DUCT STATIC PRESSURE SETPOINT (INCHES W.G.)
- SUPPLY DUCT STATIC PRESSURE (INCHES W.G.)
- RETURN FAN VFD OUTPUT (% FULL SPEED)
- RETURN FAN VFD OUTPUT (% FULL SPEED)
- OUTSIDE AIR DAMPER POSITION (% OPEN)
- RELIEF AIR DAMPER POSITION (% OPEN)

THIS INFORMATION SHALL BE ACCESSIBLE TO VIEW IN GRAPHICAL FORM ON THE FMS OPERATOR WORKSTATION.


ONCE PER MONTH THE DDC FMS SHALL RECORD THE LARGEST AHU AIRFLOW WHICH OCCURRED DURING THAT MONTH, THE DATE, TIME, OUTSIDE AIR TEMP AND ALL OTHER VALUES LISTED ABOVE THAT CONSIDERED THAT THIS EVENT SHALL ALSO BE RECORDED. THIS INFORMATION SHALL BE STORED TO A MEMORY LOCATION ON THE FMS OPERATOR WORKSTATION THAT IS MAINTAINED (NOT AUTOMATICALLY OVERTWRITTEN).

AIR HANDLER REPORT GENERATION

TIPO FOR AHU-2

1 AIR HANDLING UNIT CONTROL - AHU-2

<p>Revisions:</p> <p>Date:</p>	<p>CONSULTANT</p> <p>IMEG</p> <p>18605 3rd Ave., B., 2120 Plymouth, MN 55441 P 788.432.9080 F 788.432.5090 www.imeg.com Anderson Engineering Co. Minneapolis, MN P 612.655.6666</p>	<p>ARCHITECT/ENGINEER OF RECORD</p> <p>ANDERSON</p> <p>18605 3rd Ave., B., 2120 Plymouth, MN 55441 P 788.432.9080 F 788.432.5090 www.anderson.com Anderson Engineering Co. Minneapolis, MN P 612.655.6666</p>	<p>Office of Construction and Facilities Management</p> <p>U.S. Department of Veterans Affairs</p>	<p>Drawing Title</p> <p>CONTROL DIAGRAMS</p>	<p>Phase</p> <p>BID DOCUMENTS</p>	<p>Project Title</p> <p>CONSTRUCT NEW SPS</p>	<p>Project Number</p> <p>438-460</p>
				<p>Approved:</p>	<p>FULLY SPRINKLERED</p>	<p>Location</p> <p>Sioux Falls, SD</p>	<p>Building Number</p> <p>5</p>
				<p>Issue Date</p> <p>02/14/2025</p>	<p>Checked</p> <p>DAVING</p>	<p>Drawn</p> <p>DELLE</p>	<p>Drawing Number</p> <p>MC402</p>




SEQUENCE OF OPERATION:
 CART WASHER EXHAUST FAN SHALL BE STARTED AND STOPPED BY CART WASHER'S INTEGRAL CONTROLS.
 FAN'S MAIN MONITOR CONTACTS THAT ARE PART OF THE CART WASHER CONTROL TO DETERMINE WHEN THE CART WASHER CONTROLS ARE COMMANDING INTEGRAL EXHAUST FAN TO ACTIVATE.
 WHEN FAN IS ENERGIZED TWO-POSITION DAMPER SHALL FULLY OPEN. WHEN FAN IS DE-ENERGIZED TWO-POSITION FAN SHALL FULLY CLOSE.
 ALARMS, INTERLOCKS AND SAFETIES:
 AN ALARM SHALL BE GENERATED AT THE FMCS OPERATOR WORKSTATION IN THE FOLLOWING EVENTS:
 - AN ALARM CONDITION OCCURS AT THE CART WASHER

1 CART WASHER FAN CONTROL
 NO SCALE




SEQUENCE OF OPERATION:
 EXHAUST FAN SHALL BE INTERLOCKED TO RUN CONTINUOUSLY WHEN RESPECTIVE AHU IS OPERATING.
 1-POSITION DAMPER SHALL FULLY OPEN WHEN FAN IS ENERGIZED. WHEN FAN IS DE-ENERGIZED, 2-POSITION DAMPER SHALL FULLY CLOSE.
 ALARMS, INTERLOCKS AND SAFETIES:
 AN ALARM SHALL BE GENERATED AT THE FMCS OPERATOR WORKSTATION IN THE EVENT THE FMCS COMMANDS THE EXHAUST FAN TO OPERATE AND THE CURRENT SENSING RELAY DETECTS INSUFFICIENT CURRENT DRAW.

2 EXHAUST FAN AHU INTERLOCK - EF-1 & EF-2/AB
 NO SCALE



SEQUENCE OF OPERATION:
 EXHAUST FAN SHALL BE INTERLOCKED TO RUN CONTINUOUSLY WHEN RESPECTIVE AHU IS OPERATING.
 2-POSITION DAMPER SHALL FULLY OPEN WHEN FAN IS ENERGIZED. WHEN FAN IS DE-ENERGIZED, 2-POSITION DAMPER SHALL FULLY CLOSE.
 ALARMS, INTERLOCKS AND SAFETIES:
 AN ALARM SHALL BE GENERATED AT THE FMCS OPERATOR WORKSTATION IN THE EVENT THE FMCS COMMANDS THE EXHAUST FAN TO OPERATE AND THE CURRENT SENSING RELAY DETECTS INSUFFICIENT CURRENT DRAW.

3 EXHAUST FAN AHU INTERLOCK - EF-3 & EF-4
 NO SCALE



SEQUENCE OF OPERATION:
 THE FMCS SHALL MODULATE THE SUPPLY AIR VALVE TO MAINTAIN THE VOLUMETRIC OFFSET AS SCHEDULED IN THE DRAWINGS.
 THE FMCS SHALL MODULATE THE HEATING COIL CONTROL VALVE TO MAINTAIN SPACE TEMPERATURE OF 72°F (ADJ.) WITH A 3°F (ADJ.) DEADBAND.
 THE FMCS SHALL UTILIZE FEEDBACK FROM ALL SUPPLY AIR VALVE POSITIONS TO RESET THE SUPPLY DUCT DIFFERENTIAL STATIC PRESSURE.
 ALARMS, INTERLOCKS AND SAFETIES:
 SEND AN ALARM TO THE FMCS OPERATOR INTERFACE IF THE SPACE TEMPERATURE IS 10°F (ADJ.) ABOVE OR BELOW SETPOINT.
 SEND AN ALARM TO THE FMCS OPERATOR INTERFACE IF THE SUPPLY AIR FLOW RATE IS 10% (ADJ.) ABOVE OR BELOW SETPOINT.

4 TYPE A - SUPPLY AIR VALVE
 NO SCALE

SEQUENCE OF OPERATION:
 ALL TERMINAL AIR BOXES SHALL INCORPORATE A NIGHT SETBACK SEQUENCE.
 TAB NIGHT SETBACK SHALL BE INITIATED VIA THE FMCS BASED ON THE FOLLOWING TIME SCHEDULE:
 OCCURRED MODE START: 6:00 AM (UNOCCUPIED MODE START: 8:00 AM (ADJ.))
 AT THE START OF OCCUPANCY MODE, FMCS SHALL ESTABLISH THE MIN. CFM SETPOINT OF ALL TAB TO BE EQUAL TO THE MIN. CFM VALUE SCHEDULED IN THE TAB SCHEDULE AND SHALL ESTABLISH THE ROOM TEMPERATURE SETPOINT WITH THE TAB SCHEDULE OF OPERATION THIS SHEET.
 AT THE START OF UNOCCUPIED MODE, FMCS SHALL ESTABLISH THE MIN. CFM SETPOINT OF ALL TAB TO BE EQUAL TO THE MIN. CFM VALUE SCHEDULED IN THE TAB SCHEDULE OF OPERATION THIS SHEET.
 AT THE END OF UNOCCUPIED MODE, FMCS SHALL ESTABLISH THE ROOM TEMP SETPOINTS OF COOLING SETPOINT = 65°F (ADJ.) HEATING SETPOINT = 65°F (ADJ.)
 THE ROOM TEMP SETPOINTS SHALL BE INDICATED ON THE DRAWINGS. WHEN BUTTON IS DEPRESSED, FMCS SHALL SWITCH ALL TAB INTO OCCUPIED MODE FOR 2 HOUR (ADJ.) TIME PERIOD. AT THE END OF THE TIME PERIOD, FMCS SHALL SWITCH ALL TAB BACK TO UNOCCUPIED MODE.

5 TAB NIGHT SETBACK CONTROL
 NO SCALE

TERMINAL AIR BOX REPORT & DUCT MOUNTED HOT WATER REHEAT COIL GENERATION

DOC FMCS SHALL BE PROGRAMMED TO GENERATE THE FOLLOWING REPORT BASED ON A MANUAL COMMAND FROM THE DOC FMCS WORKSTATION BY CLICKING ON A GRAPHICAL BUTTON UPON INITIATING COMMAND THE DOC FMCS SHALL COMPLETE A REPORT AS FOLLOWS:

TAB/BOX	APPROXIMATE	TEMP/POS	VALVE POS	SUP AIR TEMP ROOM	TEMP ROOM SETPOINT
SYMBOL	MAXIMUM/MINIMUM	(% OPEN)	(% OPEN)	(DEG F)	(DEG F)
...	...	80%	60%	75.1	71.1
...	72.0	72.0


WHEREAS THE SAMPLE REPORT ABOVE SHOWS ONLY A COUPLE TABS/BOXES, THE FINAL PROGRAMMED REPORT SHALL LIST ALL TABS/BOXES SERVED BY A SINGLE AHU. A SEPARATE REPORT SHALL BE PROGRAMMED FOR EACH AHU AND FOR EACH FLOOR.

AFTER THE REPORT PRINTS OUT ALL TABS/HEATING COIL DATA, THE DOC FMCS SHALL AUTOMATICALLY TOTAL ALL THE INDIVIDUAL TAB AIRFLOW TO A SINGLE VALUE.

AFTER PRINTING THE ALARM OF THE TABS/HEATING COIL AIRFLOW CFM, THE DOC FMCS SHALL THEN AUTOMATICALLY PRINT OUT THE AIR-HEATING REPORT FOR THE AHU WHICH SERVES THE TABS/HEATING COILS LISTED IN THE REPORT.

THE DOC FMCS SHALL ALLOW THE DOC FMCS OPERATOR TO ISSUE A SINGLE COMMAND THAT WILL AUTOMATICALLY CHANGE THE LOCAL SETPOINT FOR EACH TAB SERVED BY A AHU TO A SINGLE VALUE (E.G. A SINGLE COMMAND WILL SET ALL TABS/HEATING COILS SERVED BY AHU(A) TO 65°F). A SEPARATE TABS/HEATING COIL SETPOINT OVERRIDE COMMAND SHALL BE PROGRAMMED IN THE FMCS FOR EACH AHU.

6 TERMINAL AIR BOX REPORT GENERATION
 NO SCALE




SEQUENCE OF OPERATION:
 SUPPLY FAN OPERATION SHALL BE CONTROLLED BY THE FMCS THROUGH A CONTACTOR. THE UNIT SHALL MAINTAIN A ROOM AIR TEMPERATURE SETPOINT.
 WHENEVER THE ROOM AIR TEMPERATURE IS 2°F (ADJ.) ABOVE THE SETPOINT, THE FOLLOWING SHALL OCCUR:
 - THE HEATING COIL CONTROL VALVE SHALL BE CLOSED.
 - THE CHILLED WATER CONTROL VALVE SHALL MODULATE OPEN TO MAINTAIN SPACE TEMPERATURE SETPOINT.
 WHENEVER THE ROOM AIR TEMPERATURE IS 2°F (ADJ.) BELOW THE SETPOINT, THE FOLLOWING SHALL OCCUR:
 - THE CHILLED COIL CONTROL VALVE SHALL BE CLOSED.
 - THE HEATING WATER CONTROL VALVE SHALL MODULATE OPEN TO MAINTAIN SPACE TEMPERATURE SETPOINT.
 IF ROOM AIR TEMPERATURE IS MAINTAINED AND BOTH THE HEATING AND COOLING COIL VALVES ARE CLOSED, THE SUPPLY FAN SHALL BE DE-ENERGIZED. IF EITHER OF THE COIL CONTROL VALVES OPEN, THE SUPPLY FAN SHALL BE ENERGIZED.
 WHEN FLOATING C'S ARE USED, FMCS SHALL PERFORM AN AUTO-ZERO FUNCTION EVERY NIGHT DURING UNOCCUPIED TIMES. THE FMCS SHALL STAGGER AUTO-ZERO SEQUENCES SO THAT ALL VALVES DO NOT SIMULTANEOUSLY CLOSE.
 ALARMS, INTERLOCKS & SAFETIES:
 WHEN THE FIRE ALARM CONTROL PANEL INDICATES AN ALARM CONDITION, FCU SHALL SHUTDOWN.
 A WATER LEVEL DETECTION DEVICE SHALL CLOSE THE CHILLED WATER VALVE AND PREVENT SUPPLY FAN OPERATION UNTIL DETECTION OF HIGH WATER LEVELS, AND SHALL INDICATE AN ALARM TO THE OPERATOR WORKSTATION.
 FMCS SHALL INDICATE AN ALARM TO THE FMCS OPERATOR WORKSTATION IF THE FMCS COMMANDS ANY SUPPLY FAN TO OPERATE AND THE FAN CURRENT RELAY DETECTS INSUFFICIENT CURRENT FLOW.
 WHENEVER FCU IS SHUTDOWN THE FOLLOWING SHALL OCCUR:
 - SUPPLY FAN SHALL BE DE-ENERGIZED.


7 TYPE B - TAB CONTROL W/ HOT WATER REHEAT
 NO SCALE

8 FAN COIL UNIT CONTROL
 NO SCALE


9 DOMESTIC HOT WATER CONTROL
 NO SCALE




SEQUENCE OF OPERATION:
 DOMESTIC WATER HEATER CONTROL PANEL (BAGNET COMPATIBLE) SHALL MODULATE THE STREAM CONTROL VALVE TO MAINTAIN HAFU DOMESTIC HOT WATER.
 FMCS SHALL OPEN CONTROL VALVE ON COLD WATER WHEN THE WATER HEATER IS ENERGIZED. ONE OF THE TWO CONTROL VALVES SHALL ALWAYS BE OPEN TO ALLOW THE DOMESTIC HOT WATER CIRCULATION PUMP TO OPERATE.
 FMCS SHALL MONITOR THE TEMPERATURE AT THE 140°F CIRCULATION PUMP. THE CIRCULATION PUMP SHALL TURN ON WHEN THE TEMPERATURE FALLS BELOW 120°F (ADJ.) AND SHALL TURN OFF WHEN THE TEMPERATURE RISES ABOVE 120°F (ADJ.).
 FMCS SHALL MONITOR THE OUTPUT TEMPERATURE OF THE WATER HEATERS.
 FMCS SHALL MONITOR AND RECORD THE FOLLOWING INFORMATION FROM THE WATER HEATER:
 - DISPLAY THE TEMPERATURES ONCE EVERY 5 MINUTE (ADJ.) TIME INTERVAL AND RECORD IN A TREND THAT MAINTAINS DATA FOR 7 DAY (ADJ.) PERIOD. AT THE END OF THE 7 DAY (ADJ.) PERIOD THE TREND SHALL AUTOMATICALLY OVERWRITE THE EARLIEST RECORDED DATA. TREND DATA SHALL INCLUDE DATE AND TIME STAMPS. THIS INFORMATION SHALL BE ACCESSIBLE TO VIEW IN EITHER TABULAR OR GRAPHICAL FORM ON THE FMCS OPERATOR WORKSTATION.
 - ONCE PER MONTH, THE FMCS SHALL RECORD THE FOLLOWING INFORMATION TO A MEMORY LOCATION ON THE FMCS OPERATOR WORKSTATION THAT IS MAINTAINED (NOT AUTOMATICALLY OVERRITTEN) FROM THE CIRCULATION PUMPS:
 - TOTAL RUN TIME ON EACH PUMP SHOWN IN THE DIAGRAM. COORDINATE FINAL RECORDING, DISPLAY, AND ARCHIVING INFORMATION WITH THE OWNER.
 OPERATOR WORKSTATION SHALL DISPLAY PUMP CURRENT STATUS AND ALLOW OPERATOR TO ENABLE/DISABLE THE CIRCULATION PUMP.
 ALARMS, INTERLOCKS & SAFETIES:
 FMCS SHALL INDICATE AN ALARM TO THE FMCS OPERATOR WORKSTATION IN THE EVENT THE FOLLOWING OCCUR:
 - ANY WATER HEATER INDICATES AN ALARM CONDITION.
 - ANY HOT WATER CIRCULATION PUMP INDICATES AN ALARM CONDITION.
 - THE LEAVING HOT WATER TEMPERATURE IS ABOVE 140°F (ADJ.) OR BELOW 135°F (ADJ.) FOR MORE THAN 5 MINUTES (ADJ.).



SEQUENCE OF OPERATION:
 FMCS SHALL MONITOR THE OUTPUT OF THE WATER SOFTENER, REVERSE OSMOSIS (RO), AND DEIONIZED (DI) EQUIPMENT LOCATED IN THE INTERESTED LEVELS, MECHANICAL ROOM. THE PURE WATER SYSTEM CONTROLLER SHALL OPERATE THE SYSTEM AS REQUIRED.
 FMCS SHALL MONITOR AND RECORD THE FOLLOWING INFORMATION FROM THE WATER METER:
 - CALCULATE FLOW IN GPM ONCE EVERY 5 MINUTE (ADJ.) TIME INTERVAL AND RECORD IN A TREND THAT MAINTAINS DATA FOR 7 DAY (ADJ.) PERIOD. AT THE END OF THE 7 DAY (ADJ.) PERIOD THE TREND SHALL AUTOMATICALLY OVERWRITE THE EARLIEST RECORDED DATA. TREND DATA SHALL INCLUDE DATE AND TIME STAMPS. THIS INFORMATION SHALL BE ACCESSIBLE TO VIEW IN EITHER TABULAR OR GRAPHICAL FORM ON THE FMCS OPERATOR WORKSTATION.
 - ONCE PER MONTH, THE FMCS SHALL RECORD THE FOLLOWING INFORMATION TO A MEMORY LOCATION ON THE FMCS OPERATOR WORKSTATION THAT IS MAINTAINED (NOT AUTOMATICALLY OVERRITTEN) FROM THE CIRCULATION PUMPS:
 - DATE, TIME AND HIGHEST RECORDED FLOW RATE IN GPM (CALCULATED OVER A 5 MINUTE TIME PERIOD).
 - TOTAL VOLUME IN GALLONS OF SOFTENED WATER.
 ALARMS, INTERLOCKS AND SAFETIES:
 - AN ALARM SHALL BE GENERATED AT THE FMCS OPERATOR INTERFACE IF ANY OF THE PURE WATER SYSTEM CONTROLS INDICATE AN ALARM.



11 AIR COMPRESSOR CONTROL DIAGRAM
 NO SCALE




12 EMERGENCY SHOWER/EYEWASH MONITORING
 NO SCALE

CONSULTANT 		ARCHITECT/ENGINEER OF RECORD 		STAMP 	Office of Construction and Facilities Management 	Drawing Title CONTROL DIAGRAMS	Phase BID DOCUMENTS	Project Title CONSTRUCT NEW SPS	Project Number 438-460
Revisions: _____ Date: _____		13605 3rd Ave., B. 8130 Pflugerville, VA 20141 P 783.432.4080 F 788.432.4090 JAB-MB-CR14 Anderson Engineering Group, LLC PWS # 16084		Approved: _____	U.S. Department of Veterans Affairs	Approved: _____	FULLY SPRINKLERED	Location Sluox Falls, SD	Building Number 5
						Issue Date 02/14/2025	Checked DAVING	Drawn DELLE	Drawing Number MC403

2/14/2025 10:25:10 AM
 \\va\hmc\ccm\Drawings\SPS\SPS\021425\021425_001.dwg
 2/14/2025 10:25:10 AM
 \\va\hmc\ccm\Drawings\SPS\SPS\021425\021425_001.dwg

- GENERAL PLUMBING NOTES:**
1. REFERENCE P001 - PLUMBING COVER SHEET FOR PLUMBING SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES.
 2. EXISTING CONDITIONS ARE SHOWN BASED ON INFORMATION OBTAINED FROM FIELD SURVEYS, EXISTING BUILDING DOCUMENTS, AND STAFF. VERIFY EXISTING CONDITIONS AND REPORT ANY CONFLICTS BEFORE PROCEEDING.
 3. G.C. SHALL CUT AND PATCH EXISTING AS REQUIRED FOR NEW WORK. REFERENCE SPECIFICATION SECTION 22 05 06 FOR COMPLETE LAYOUT DRAWINGS SHALL BE REQUIRED BY SPECIFICATION SECTION 22 05 11. CONSTRUCTION WORK SHALL NOT BEGIN UNTIL SYSTEM LAYOUT DRAWINGS HAVE BEEN APPROVED BY THE C.O.R.
 4. CONTRACTOR SHALL MINIMIZE DOWNTIME OF EXISTING SYSTEMS BY INSTALLING NEW SYSTEMS PRIOR TO TYPING INTO EXISTING. NOTIFY C.O.R. A MINIMUM OF 24 HOURS PRIOR TO SYSTEM SHUT/DOWN.
 5. DEMOLISH ALL EXISTING HANGERS, REGULATION, VALVES, AND ACCESSORIES ASSOCIATED WITH MECHANICAL EQUIPMENT AND PIPING SHOWN TO BE REMOVED ON THESE PLANS UNLESS OTHERWISE NOTED.
 6. DEMOLISH ALL EXISTING CONTROL DEVICES, WIRING, AND CONSULT ASSOCIATED WITH MECHANICAL EQUIPMENT SHOWN TO BE REMOVED ON THESE PLANS UNLESS OTHERWISE NOTED.
 7. NOT ALL MECHANICAL DEMOLITION IS EXPLICITLY SHOWN ON THE DRAWING. CONTRACTOR SHALL CONFIRM EXTENT OF DEMOLITION AT THE SITE.



FIRST LEVEL DEMOLITION PLAN - PLUMBING
1/8" = 1'-0"

2/14/2025 10:31:13 AM
 2/14/2025 10:31:13 AM
 2/14/2025 10:31:13 AM

Revisions:	Date:

CONSULTANT

IMEG

1800 SOUTH STREET
 BOX 100000
 FARGO, ND 58103
 701.785.4444
 WWW.IMEG.COM


PROJECT # 1800000000

SCALE: AS SHOWN

ARCHITECT/ENGINEER OF RECORD

ANDERSON

186DS 3rd Ave. W., 2120 FARGO, ND 58441
 P 785.432.4000 | F 785.432.4500 | WWW.ANDERSON.COM
 Anderson Engineering & Architecture, LLC | PEOB # 16004



Office of Construction and Facilities Management

VA U.S. Department of Veterans Affairs

Drawing Title	Project Title
FIRST LEVEL DEMOLITION PLAN - PLUMBING	CONSTRUCT NEW SPS
Approved:	

Phase	Location
BID DOCUMENTS	Sioux Falls, SD
FULLY SPRINKLERED	Issue Date: 02/14/2025
	Checked: NAT/JAC
	Drawn: DELLE

Project Number	Drawing Number
438-460	PLD111
Bidding Number	
5	

